

2

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 13 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Tenneco Oil Company

Complete Address 2000 Classen Center Oklahoma City, Oklahoma 73106

Lease Name P. C. Schultz Well No. 1-35

Location NE NE SE Sec. 35 Twp. 20 Rge. (E) (W) 36

County Pawnee Total Depth 3870'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 10 A Day 11 Month 9 Year 1973

The above well was plugged as follows:

Total Depth 3870' 8 5/8 csg set at 1047' cwc:

5 1/2 csg set at 3869' cw 125 sk.

5 1/2 csg PBDT 3854' with perf. (3789-3791):

Filled 5 1/2 csg W/sd (3750-3854) Dumped 5 sk cmt W/dump bailer. (3715-3750)

Cutoff and recovered 2700' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 365' -set rock & sand bridge (350-365)

Dumped 5 yds readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Messing  
Well Plugging Supervisor

DATE 9-13-73

INV. NO. 7909-112