

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -145 -20472.0000 (of this well)

Operator's Full Name E. K. Edmiston Oil Co., Inc.

Complete Address 600 Vickers KSB&T Bldg., Wichita, Ks, 67202

Lease Name Franklin Well No. 1

Location NW NW NE Sec. 35 Twp. 20 Rge. (E) (W) 16

County Pawnee Total Depth 3775'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 2:15 P Day 16 Month 4 Year 1979

The above well was plugged as follows:

TD 3775' 8 5/8 csg set 1024' cwc 450 sk.

4 1/2 csg set 2771' cw 150 sk cem.

Filled 4 1/2 csg with sand (3775'-3700') dumped 3 sk cem W/dump bailer. (3700'-3670')

Cutoff & recovered A/3006' of 4 1/2 csg.

Edlg mud TD-565'- Set rock & sand bridge (565'-550')

Filled from 550' to base of cellar with 8 yds readymi~~x~~ cem.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4-18-79

INV. NO. 9451.0

Signed: [Signature]
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1979
CONSERVATION DIVISION
Wichita, Kansas