



15.159.20551.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

May 20, 1975

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

5-29-75 MAY 29 1975

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bill Luck of Northern Natural Gas Co. has this
date requested permission to plug the following described well:

Mr. Luck guarantees payment of the plugging fee.

Operator's full Name: Northern Natural Gas Company

Complete Address: P.O. Box 88, Lyons, Kansas 67554

Lease Name: Hollinger Well No. OB14-01

Location: 2415' FEL 1399' FSL Sec. 14 Twp. 20 Rge. 8 (E) (W) X

County: Rice Total Depth 4200' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Observation
Well

Mr. Luck was instructed to plug the well as follows:

This is a directional observation well--temporarily abandoned.

Fill hole with mud. Pump 50 sacks cement at 3940'.

(Fill 3940'-3740') Set Baker plug at 1000'. (Cast iron-
drillable plug) Push Halliburton plug to 90' and circulate
cement from 90' to surface.

Very truly yours,

[Signature]
Conservation Division Agent