

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-009-21,982.0000

LEASE NAME Kenneth Scheufler

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 9 TWP. 20S RGE. 11W ~~(E)~~ or (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 5-6-92

Plugging Completed 5-11-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Resource Operations

ADDRESS P.O. Box 466 Chase, Kansas 67524

PHONE#(316) 938-2982 OPERATORS LICENSE NO. 30364

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	630'	none
				4 1/2"	3399'	2205'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3245' ran 4 sacks cement. Shot pipe @2618', 2412', 2205'.
Mixed 500# hulls in with 100 sacks cement @800', pulled to 400' and 100
sacks cement circulated to top 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Resource Operations

STATE OF Kansas COUNTY OF Rice, ss. 5-17-92

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 13 day of May

Irene Herzberg
 Notary Public

My Commission Expires:



15.009.21982.0000

Hetro-Log

Radiation Guard Log

COMPANY <u>FELL AND WOLFE OIL COMPANY</u>	
WELL <u>KENNETH SCHEUFLER #1</u>	
FIELD _____	
COUNTY <u>BARTON</u>	STATE <u>KANSAS</u>
Location <u>C/N/2-NW-NE</u>	Other Services: <u>CDL</u>
Sec. <u>9</u> Twp. <u>20S</u> Rge. <u>11W</u>	
Permanent Datum: <u>GROUND LEVEL</u> Elev. <u>1767</u>	Elev.: K.B. <u>1779</u>
Log Measured From <u>K.B.</u> , <u>12</u> Ft. Above Perm. Datum	D.F. _____
Drilling Measured From <u>KELLY BUSHING</u>	G.L. <u>1767</u>

Date	9/27/80				
Run No.	ONE				
Depth—Driller	3400				
Depth—Logger	3397				
Btm. Log Inter.	3396				
Top Log Inter.	SURF.				
Casing—Driller	8 5/8 @ 630	@	@	@	@
Casing—Logger					
Bit Size	7 7/8				
Type Fluid in Hole	CHEMICAL				
Dens. Visc.	9.6 53				
pH Fluid Loss	11.0 13.2 ml		ml		ml
Source of Sample	FLOWLINE				
R ₁ @ Meas. Temp.	.21 @ 70 °F	@	°F	@	°F
R ₂ @ Meas. Temp.	.16 @ 70 °F	@	°F	@	°F
R ₃ @ Meas. Temp.	.32 @ 70 °F	@	°F	@	°F
Source: R ₁ R ₂ R ₃	CHARTS				
R ₄ @ BHT	.13 @ 111 °F	@	°F	@	°F
Time Since Circ.	2 HOURS				
Max. Rec. Temp.	111 °F		°F		°F
Equip. Location	H-101 GB				
Recorded By	M. JACOBS AND S. MAYERS				
Witnessed By	MR. WAYNE LEBACK				

APR 24 1982
 U.S. ENVIRONMENTAL PROTECTION AGENCY
 DIVISION
 Wichita, Kansas