

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Pawnee County. Sec. 35 Twp. 20S Rge. 16 (E) W(W)
Location as "NE/CNW%SW%" or footage from lines NW NE NE
Lease Owner Vickers Explorations, Ltd.
Lease Name Franklin Well No. 1
Office Address Box 2240, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed May 13, 1953
Application for plugging filed May 12, 1953
Application for plugging approved May 12, 1953
Plugging commenced May 13, 1953
Plugging completed May 13, 1953
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3832 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1048	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 300' Dump 20 sx cement. Fill hole with mud to 35'
Set plug and dump 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1953
5-21-53
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Jayhawk Drilling Co., Inc.
Address Box 2240 Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. John M. Little (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John M. Little
Box 2240 Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 1953

My commission expires August 13, 1953 Allen P. Denton Notary Public.

PLUGGING
FILE SEC 35 T 20 R 16W
BOOK PAGE 101 LINE 11

Franklin Well #1
NW NE NE Sec. 35-20S-16W
Pawnee County, Kansas

Casing Record
8 5/8" @ 10 1/8" w/ 450 sx

Commenced: April 30, 1953
Completed: May 13, 1953

Elevation: 2052 R.B.

D & A

LOG

Surface & Clay	0-370
Clay	370-445
Sand	445-580
Red Beds, Shale	580-1010
Shale	1010-1046
Anhydrite	1046-1070
Shale	1070-1535
Salt & Shale	1535-1760
Lime & Shale	1760-1835
Shale & Lime	1835-2010
Lime & Shale	2010-2135
Lime	2135-2255
Lime & Sand	2255-2335
Lime & Shale	2335-2855
Shale & Lime	2855-3195
Lime	3195-3285
Lime & Shale	3285-3303
Black Shale	3303-3305
Lime	3305-3403
Black Shale	3403-3407
Lime & Shale	3407-3419
Lime	3419-3432
Shale	3432-3489
Lime & Shale	3489-3500
Lime	3500-3769
Chert & Shale	3769-3784
Shale & Sandy Shale	3784-3815
Dolomite	3815-3832

Schlumberger Tops:

Heebner	3402
Toronto	3418
Douglas	3431
Brown Lime	3489
Lansing	3500
Cherty Congl.	3769
Simpson Shale	3784
Arbuckle	3815

No Shows

RECEIVED
MAY 20 1953

I hereby certify that this log is true and correct to the best of my knowledge and belief.

VICKERS EXPLORATIONS, LTD.

By Lyle Thomas

Subscribed and sworn to before me this 19th day of May, 1953.

Allan P. Denton
Notary Public

My Commission expires August 13, 1953.

PLUGGING
FILE SEC 35-20-R-16W
BOOK PAGE 201-LINE 11