


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

PAWNEE County, Sec. 35 Twp. 20S Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines. SW SW NW
Lease Owner APACHE OIL CORP.
Lease Name BRADLEY Well No. 1
Office Address 823 South Detroit, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 1, 1961
Application for plugging filed June 1, 1961
Application for plugging approved June 1, 1961
Plugging commenced June 1, 1961
Plugging completed June 1, 1961
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, 222 So. Main, St. John, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3770 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale, Red Bed, Sand & Anhy.	Surf. Csg.	-0-	1002'	8-5/8"	1002'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: Filled hole with heavy mud from 3770' up to 350'.
Set bridge using 1/3 sk. hulls, Halliburton plug,
20 sx. cement through drill pipe. Filled hole
with mud up to 35'. Set bridge using 1/2 sk.
hulls, Halliburton plug, 10 sx. cement to Cellar
Zero.

Job Completed: 2:15 p.m. 6-1-61

RECEIVED
STATE CORPORATION COMMISSION

6-5-61 JUN 5 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 208 Petroleum Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.
C. T. HONAKER, DRILLING SUPERINTENDENT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRIG. SUPT.

Box 232, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 19 61

My commission expires 10-17-63

Geroy Dietz
Notary Public.

15.145.00455.0000

APACHE OIL CORP. - Operator

SIERRA PETROLEUM CO., INC - Contractor

BRADLEY #1
SW SW NW
Sec. 35-20S-16W
Pawnee County, Kansas

T. D.: 3770'
Elev.: 1998' K.B.

Casing:

8-5/8" Set at 1002' K.B.

Cement:

with 500 sx. cement

Commenced Drilling: 5-19-61
Completed Drilling: 6-1-61

FORMATION	DEPTH
Shale	490
Sand	535
Shale	700
Red Bed	740
Red Bed	996
Anhydrite	1002
Anhydrite	1022
Shale & Shells	1350
Shale & Salt	1560
Shale & Shells	1770
Lime & Shale	1855
Lime	1970
Lime & Shale	3094
Lime	3154
Shale & Lime	3262
Lime	3658
Lime & Shale	3766
Lime	3770

TOPS:

Anhydrite	996
Heebner	3345
Brown Lime	3427
Lansing K. C.	3488
Arbuckle	3756

STATE OF KANSAS)
COUNTY OF RUSSELL) ss:

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1961
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above information is true
and correct to best of my knowledge.

C.T. Honaker

Subscribed and sworn to before me this 2nd day of June
1961.

Leroy Ditz
Notary Public

My commission expires: 10-17-63