

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.145.20447.0000

LEASE NAME Bradley #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NE NE NW

SEC. 35 TWP. 20 RGE. 16 W(E) or (W)

COUNTY Pawnee

Date Well Completed \_\_\_\_\_

Plugging Commenced 1-19-84

Plugging Completed 1-25-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Edmiston Oil Company

ADDRESS 818 E. 10th Great Bend, Kansas 67530

PHONE # ( ) \_\_\_\_\_ OPERATORS LICENSE NO. 5042

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3788'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				3-5/8"	1021'	none
				4-1/2"	3788'	2695'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with 4 sacks cement, sand to 3700' and 4 more sacks cement. Shot casing @ 3031', 2921', 2819', 2695' and pulled a total of 75 (2695') joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 75 cement, 15 gel, 1 hull, released plug and displaced with 125 cement, 60/40 pos, 2% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the information above-described well as filed that the same are true and correct before me, a Notary Public, in and for the State of Kansas.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

JAN 30 1984

CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 27 day of January, 1984



Irene Hoover  
Notary Public

My Commission expires: \_\_\_\_\_

5049

15.145.20447.0000

**Electra**  
Inc.

**RADIATION  
ACCURLOG**

35 20s 16w

COMPANY EDMISTON OIL COMPANY

WELL BRADLEY # 1

FIELD WILLOCAT

COUNTY PAWNEE STATE KANSAS

Location NE NE NW Other Services:

Sec. 35 Twp. 20S Rgn. 16W

Permanent Datum: GROUND LEVEL, Elev. 2012 Elev.: K.B. 2017

Log Measured From R.B. 5 Ft. Above Perm. Datum D.P. 2019

Drilling Measured From KELLY BUSHING G.I. 2012

Date	<u>1-23-77</u>	<u>GAMMA RAY</u>	<u>NEUTRON</u>	<u>ACCURLOG</u>	<u>CALIPER</u>
Run No.	<u>ONE</u>	<u>ONE</u>	<u>ONE</u>	<u>ONE</u>	<u>ONE</u>
Depth—Driller	<u>3789</u>	<u>3781</u>	<u>3781</u>	<u>3781</u>	<u>3781</u>
Depth—Logger	<u>3784</u>	<u>3784</u>	<u>3784</u>	<u>3784</u>	<u>3784</u>
Btm. Log Inter.	<u>3776</u>	<u>3784</u>	<u>3779</u>	<u>3772</u>	<u>3772</u>
Top Log Inter.	<u>0</u>	<u>0</u>	<u>3200</u>	<u>3200</u>	<u>3200</u>
Casing—Driller	<u>8 7/8 @ 1021</u>	<u>@</u>	<u>@</u>	<u>@</u>	<u>@</u>
Casing—Logger					
Bit Size	<u>7 7/8</u>				
Type Fluid in Hole	<u>WATER BASE</u>				
	<u>STARCH MUD</u>				
Dens.	<u>10.6</u>	<u>51</u>			
Visc.					
pH	<u>6.4</u>	<u>7.5</u>	<u>ml</u>	<u>ml</u>	<u>ml</u>
Fluid Loss					
Source of Sample	<u>FLOW LINE</u>				
R <sub>1</sub> @ Meas. Temp.	<u>22 @ 73 °F</u>	<u>@</u>	<u>*F</u>	<u>@</u>	<u>*F</u>
R <sub>2</sub> @ Meas. Temp.	<u>16 @ 73 °F</u>	<u>@</u>	<u>*F</u>	<u>@</u>	<u>*F</u>
R <sub>3</sub> @ Meas. Temp.	<u>@ *F</u>	<u>@</u>	<u>*F</u>	<u>@</u>	<u>*F</u>
Source: R <sub>1</sub> R <sub>2</sub>	<u>CHARTS</u>				
R <sub>1</sub> @ BHT	<u>15 @ 107 °F</u>	<u>@</u>	<u>*F</u>	<u>@</u>	<u>*F</u>
Time Since Circ.	<u>NONE</u>				
Max. Rec. Temp.	<u>107</u>	<u>*F</u>	<u>*F</u>	<u>*F</u>	<u>*F</u>
Equip.   Location	<u>134 KANSAS</u>				
Recorded By	<u>GORDON YOUNG</u>				
Witnessed By	<u>MARVIN FRANKAMP</u>				

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1984

CONSERVATION DIVISION  
Wichita, Kansas