


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County, Sec. 35 Twp. 20 Rge. 16 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
NW NWNE  
Lease Owner E. K. Edmiston  
Lease Name Franklin #1 Well No. \_\_\_\_\_  
Office Address Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 4/12/79 19\_\_\_\_  
Plugging completed 4/16/79 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3775  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1024	none
				4 1/2"	3771	3000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 3750' and ran 3 sacks cement. Shot pipe at 3003', pulled 91 joints. Set rock bridge at 560' and ready mix well from 560 to 0 with 8 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 79

Margaret Melcher  
Notary Public.

My commission expires \_\_\_\_\_



RECEIVED  
STATE CORPORATION COMMISSION

APR 20 1979

CONSERVATION DIVISION  
Wichita, Kansas

## DRILLERS' WELL LOG

DATE COMMENCED: July 31, 1977  
 DATE COMPLETED: August 9, 1977

Edmiston Oil Co.  
 FRANKLIN # 1  
 NW NW NE  
 Sec 35-T20-R16W  
 Pawnee County, Kansas

AUG 19 1977

ELEVATION: 2026 K.B.

0 - 25' Surface Soil, Clay  
 25 - 661' Shale, Sand  
 661 - 1018' Red Bed  
 1018 - 1038' Anhydrite  
 1038 - 1932' Shale  
 1932 - 3457' Lime and Shale  
 3457 - 3678' Lime  
 3678 - 3771' Lime and Shale  
 3771 - 3775' Dolomite  
 3775' RTD

## FORMATION TOPS

Anhydrite	1018
Heebner	3361
Brown Lime	3447
Kansas City	3457
Base K.C.	3678
Arbuckle	3771
RTD	3775

## SURFACE PIPE:

Set used 8 5/8", 28# pipe at  
 1024' w/250 sacks 50/50 Pozmix,  
 2% Gel, 3% cq followed with  
 200 sacks Common, 2% Gel, 3% cc.

## PRODUCTION PIPE:

Ran new 4 1/2", 9 1/2# casing at  
 3771' w/150 sacks 50/50 Pozmix,  
 2% Gel, salt sat. w/10 bbl  
 salt flush ahead.

## A F F I D A V I T

STATE OF KANSAS }  
 COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and  
 statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 10th day of August, 1977.

Alvord M. Hague  
 Notary Public

My Commission Expires: April 11, 1978

RECEIVED  
 STATE CORPORATION COMMISSION

APR 16 1979

CONSERVATION DIVISION  
 Wichita, Kansas