

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pawnee County, Sec. 35 Twp. 20S Rge. 16 ~~(E) W~~ (W)
Location as "NE/CNWxSWx" or footage from lines C E/2 SE NE
Lease Owner Tenneco Oil Company
Lease Name Franklin Well No. 1-35
Office Address 2000 Classen Center, Oklahoma City, Oklahoma 73106
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 21 1971
Application for plugging filed February 20 1971
Application for plugging approved February 20 1971
Plugging commenced February 20 1971
Plugging completed February 21 1971
Reason for abandonment of well or producing formation No Productible Zone

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3960 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1050	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gunned up pits forming heavy mud, filled hole to 600 feet, spotted 40 sacks cement. Filled hole to 250 feet, spotted 25 sacks cement. Filled hole to 40 feet, pushed plug to 40 feet, capped with 10 sacks cement. Job complete at 1:15 AM February 21, 1971.

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1971
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address Box 1164, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
Ben E. Unruh (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben E. Unruh
Box 1164, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of March, 1971
James A. [Signature]
Notary Public.

My commission expires July 8 1972



WELL LOG

15.145.20197.0000

COMPANY Tenneco Oil Company
 FARM J. L. Franklin NO. 1-35
 TOTAL DEPTH 3960'
 COMM. 2-12-71 COMP. 2-21-71
 CONTRACTOR Garvey Drilling Company

SEC. 35 T. 20S R. 16W
 LOC. C E/2 SE NE
 COUNTY Pawnee, Kansas

CASING
 8 5/8" @ 1050' w/450sx

ELEVATION
 PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 480' Shells & Shale
- 592' D-sand
- 730' Shale
- 1044' Shale & Shells
- 1050' Anhydrite
- 1569' Shale & Shells
- 1926' Shale & Lime
- 2000' Lime
- 2230' Lime & Shale
- 2675' Shale & Lime
- 3195' Lime & Shale
- 3630' Lime
- 3800' Arbuckle
- 3960' Chert & Lime
- 3960' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 APR 29 1971
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas }
 County of Barton } SS

I, Charlene Marker of Garvey Drilling Company
 upon oath state the above and foregoing is a true and correct copy of the log of the J. L. Franklin No. 1-35 well.

Subscribed and sworn to before me this 2nd day of March 19 71

My Commission Expires: July 8, 1974

Charlene Marker
James R. [Signature]
 NOTARY PUBLIC