


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 14 Twp. 20S Rge. XXXX(B) 8 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW
Lease Owner Smitherman & Cohen Drilling Company
Lease Name Stahl Well No. 4
Office Address P. O. Box 692 El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12 - 14 1949
Application for plugging filed 4 - 10 1952
Application for plugging approved 4 - 17 1952
Plugging commenced 4 - 27 1952
Plugging completed 5 - 1 1952
Reason for abandonment of well or producing formation Oil depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee
Producing formation Sand Depth to top 3322 Bottom 3329 Total Depth of Well 3337 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"		2808'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rocked hole from 3257' to 3220' and ran
6 sacks of cement. Pumped in 25 sacks of
cement. Mudded hole to 40' and ran 10
sacks of cement. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
L. C. Smitherman (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. SMITHERMAN & COHEN DRILLING COMPANY

(Signature) *L. C. Smitherman*

P. O. Box 692 El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 1952.

Edith A. Bissett
Notary Public.

My commission expires March 3, 1955

23-8390-s 6-51-20M
PLUGGING
FILE SEC 14 T 20 R 8 W
BOOK PAGE 9 LINE 11

STAHL WELL #4

166' - 8 5/8" - 135 sx
 3324' - 5 1/2" - 75 sx

Allan & Brooks
 NW NW SW 14-20-8W
 Lyons Pool, Rice County, Kansas
 Comm: 11/20/49 Compl: 12/14/49
 Contractor: Tom Allan
 Elevation: 1642
 I.P. Swab 4 bbl. oil per hour

0 -	65	Soil, Sand, & Gravel
	165	Red Beds
	176	Anhydrite
	500	Red Beds
	750	Shale
	1000	Salt & Shale
	1200	Anhydrite & Shale
	1400	Dolomite & Lime
	2280	Shale & Shells
	2700	Lime & Shale Breaks
	2804	Shale with Thin Sands
	2811	Brown Lime
	2820	Shale
	2827	Sandstone
	2834	Shale
	2865	Lime & Shale Breaks
	2873	Soft Oolitic Lime
	2880	Lime
	2910	Shale & Lime Streaks
	2941	Lime
	2956	Soft Oolitic Lime
	3009	Lime with Shale Streaks
	3016	Soft Oolitic Lime
	3025	Lime
	3035	Shale
	3039	Lime
	3055	Lime Partly Oolitic
	3080	Lime & Shale Breaks
	3083	Soft Oolitic Lime
	3115	Lime
	3125	Cherty Lime
	3145	Lime
	3160	Shale
	3170	Lime
	3190	Shale & Lime Shells
	3203	Red Shale
	3225	Red Shale Conglomerate
	3234	Varicolor Chert Conglomerate
	3322	Red & Gray Shale
	3324	Sand
	Ran Casing,	3324 = 3327 S.L.M.
	3329	Sand
	3332	Mud Lime & Dolomite
	3337	Dolomite

FORMATIONS

165	Top Anhydrite
2834	Top Lansing
3203	Top Conglomerate
3322	Top Misener
3329	Top Maquoketa

RECEIVED
 STATE CORPORATION COMMISSION

MAY 16 1952

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 14 T 20 R 1 W
 BOOK PAGE 9 LINE 4