


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rice County, Sec. 34 Twp. 20 Rge. (E) 8 (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNWxSWx" or footage from lines NW NW SE
Lease Owner Thos. H. Allan, et al
Lease Name Fred Ray Well No. 1
Office Address 1221 Union National Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 16 1955
Application for plugging filed February 16 1955
Application for plugging approved February 16 1955
Plugging commenced February 16 1955
Plugging completed February 17 1955
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Tested - Mississippi Depth to top 3274 Bottom 3315 Total Depth of Well 3317 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 173' | None |
| | | | | 5 1/2" | 3280' | 2747' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back 3317' to 3310' - Before Water Frac

| | |
|--------------|------------------|
| 3310 - 3260 | 6 sacks cement |
| 3260 - 170 | Heavy Rotary Mud |
| 170 - 165 | Rock Bridge |
| 165 - 125 | 15 sacks cement |
| 125 - 25 | Heavy Rotary Mud |
| 25 - Surface | 5 sacks cement |

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1955 2-24-55

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thos. H. Allan
Address 1221 Union National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Thos. H. Allan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Thos. H. Allan

1221 Union National Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of February, 1955

Ocie M. Stewart

My commission expires June 14, 1958

Notary Public.

PLUGGING
FILE SEC. 34 TWP. 20 R. 8W
BOOK PAGE 28 LINE 22

8 5/8" @ 173 - 140 Sx
5 1/2" @ 3280 - 75 Sx - 2747 Pilled

ALLAN, HINKLE ET AL #1 FRED RAY
NW SE 34-20-8W
Rice County, Kansas
COMM: 1/30/55 COMPL: 2/16/55
CONTRACTOR: Tom Allan
ELEVATION: 1659 RB

I.P. D & A

All Depths From Rotary Bushings

0 - 20 Soil
90 Gravel
120 Yellow Clay
173 Red Beds
500 Red Rock
700 Shale
1000 Salt & Shale
1100 Anhydrite
2400 Shale & Shells
2750 Lime & Shale partings
2755 Black Shale
2760 Buff Lime
2790 Sandy Shale
2890 Shale
2899 Lime Brown
2916 Sandy Shale
2935 Lime White
2955 Lime & Shale
2980 White Lime
3025 Lime & Shale
3031 Collicastic Lime
3116 Lime
3125 Collicastic Lime
3160 Lime
3180 Shale
3220 Lime
3240 Shale & Lime
3274 Lime & Vary Color Shale
3300 White Vitreous Chert
Ran Casing to 3280
Changed to Cable Tools
3315 Partly Weathered ~~Chert~~ Chert
and Petroleum Residue
3317 (T.D.) Red Mud

FORMATION TOPS:
2750 Heebner
2890 Brown Lime
2916 Lansing
3274 Mississippi
3315 Kinderhook

I certify that the above is a true and correct copy of the well log on the above test.

Tom Allan

Subscribed and sworn to before me this 22nd day of February, 1955

Ocie M. Stewart
Notary Public

My Commission expires June 14, 1958

Plugged back to 3310
Water Frac 253 bbl. Water
4000# Sand - 1400# Pressure
Small showing of gas

RE
STATE CORP.

FEB 24 1955

CONSERVATION DIVISION

Wichita, Kansas
PLUGGING
FILE SEC 34 20 R 8W
BOX PAGE 98 LINE 22