

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bly Building  
Wichita, Kansas

Rice County. Sec. 34 Twp. 20 Rge. 11 (W) 8 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SW

Lease Owner. Ingling & Parker

Lease Name. Evans 8 Well No. 1

Office Address. Fourth Nat'l Bank Bldg.

Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole

Date well completed. 19

Application for plugging filed. 11-20-43 19

Application for plugging approved. 11-20-43 19

Plugging commenced. 11-12-43 19

Plugging completed. 11-12-43 19

Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. Dry Hole 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Ruel Durkee

Name of Conservation Agent who supervised plugging of this well.

Producing formation. Depth to top. Bottom. Total Depth of Well. 3580 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 1/2"	157	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom previously cemented off. Four sacks cement dumped at 3360'  
10 sacks cement dumped at 157'. 5 sacks cement at base of cellar.  
Filled with mud between cement plugs.

2-10-48



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Ingling & Parker  
Address. Fourth Nat'l Bank Bldg.  
Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgewick, ss.  
I, W. W. Henry, Jr. (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
(Address) 2nd South Nat'l Bldg Wichita Kan

SUBSCRIBED AND SWORN TO before me this day of 19

My commission expires Notary Public.

PLUGGING  
FILE SEC 34 T 20 R 8 W  
BOOK PAGE 98 LINE 22

WELL LOG EVANS NO. 1

Ingling & Parker: Lease Owners

Sec. 34, Twp. 20, Rge. BW

Ingling & Parker: Contractors

Location: C SW NW SW

Total Depth: 3580'

County: Rice County, Kansas

Commenced: Sept. 5, 1942

Elevation: 1658'

Casing: 157' of 8 5/8" OD  
3496' of 4 1/2" OD

Production:

Figures below indicate bottom of formation

Sand & Clay	157	Top Lansing	2899
Red Bed Lime Shells	415	Lime	3062
Shale & Shells	775	Broken Lime Shale	3110
Shale	830	Shale	3116
Salt Shale Shells	1008	Lime Hard	3150
Shale Shells Sand	1125	Base Kansas City	3209
Sand	1135	Shale & Lime	3215
Lime Shale	1225	Lime Shale Broken	3260
Lime	1285	Top Conglomerate	3272
Lime Shale	1400	Conglomerate	3295
Broken Lime Sand	1430	Lime Hard	3305
Broken Lime	1612	Conglomerate	3330
Lime & Shale	1740	Chert	3343
Shale Lime Shells	1905	Conglomerate Lime Shale	3370
Lime & Shale	1990	Top Misener	3377
Shale & Shells	2230	Hard White Sand	3381
Shale	2415	Sand Cored	3391
Lime	2475	Base Misener Sand	3414
Broken Lime	2515	Lime & Shale	3428
Lime & Shale	2560	Top Viola	3430
Broken Lime	2610	Lime	3470
Lime	2460	Lime Hard	3476
Shale	2663	Top Simpson	3478
Hard Lime	2684	Sand Shale	3500
Broken Lime	2830	Sandy Shale	3515
Shale	2876	Shale	3535
Sandy Lime	2883	Top Arbuckle	3540
Hard Lime	2895	Broken Lime	3580 T.D.
Top Lansing	2899		

We hereby certify that this is a true and correct log of the above mentioned well.

Ingling & Parker  
D. T. Ingling

(Original Signed)

STATE OF KANSAS)  
COUNTY OF SELGWICK) ss.

Partner

Subscribed and sworn to before me, a Notary Public in above said County and State, this 6th day of October, 1942.  
My commission expires

Notary Public

10/16/42 - copy to  
Deep Rock

10/6 - notary copy to (Deep Rock) +  
Midstate

PLUGGING

FILE SEC 34 T 20 R 8W  
BOOK PAGE 98 LINE 22

Copy to Shell Log Bureau  
10/9 notarized copy to Layman for Margay  
10/10 - copy to Shell Log Bureau  
10/10 - 2 copies - Mrs. Layman