

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rice County. Sec. 33 Twp. 20 Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE  
Lease Owner Raymond Oil Company, Inc.  
Lease Name Schafer Well No. 1  
Office Address 410 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 4, 1967 19  
Application for plugging filed March 27, 1967 19  
Application for plugging approved March 22, 1967 19  
Plugging commenced March 14, 1967 19  
Plugging completed March 14, 1967 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	214'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill hole with mud to 200 feet, Set Plug and 1/4 sx hulls - 25 sx cement; Fill hole w/mud to 40 feet, set plug - 1/2 sx hulls, 10 sx cement- 25 sx cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 28 1967 3-28-67

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Raymond Oil Company, Inc.  
Address 410 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Chas. W. Raymond (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Chas W Raymond  
410 Fourth National Bank Bldg., Wichita, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 24th day of March, 19 67

My commission expires February 15, 1971



Ronnie Donnelly  
Ronnie Donnelly - Notary Public

15.159.26015.0000

RAYMOND OIL COMPANY, INC.  
#1 SCHAFFER  
NW SW SE, Sec. 33-20S-8W  
Rice County, Kansas

ELEVATION: 1662 KB  
1660 DF  
1657 GL

Drilling Contractor: Company Tools  
Date Commenced: March 4, 1967  
Date Completed: March 14, 1967

Casing Record  
214' 8-5/8" w/250 sx.

Figures Indicate Bottom of Formations

<u>Formation</u>	<u>Depth</u>
Sand	158
Shale & Red Bed	214
Shale	800
Shale & Shells	1050
Shale & Lime	1431
Lime & Shale	1870
Shale & Lime	2314
Lime & Shale	2941
Lime	3229
Lime & Shale	3294
Lime, Shale & Sand	3320
Sand	3334
Shale & Sand	3390
Lime & Shale	3452
Lime, Shale & Sand	3504
Lime & Shale	3559
Arbuckle	3570
RTD	3570

RECEIVED  
OIL CORPORATION COMMISSION

MAR 28 1967

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
) SS  
COUNTY OF SEDGWICK )

I hereby certify that the above is true and correct to the best of my knowledge.

Wm. M. Raymond

Subscribed and sworn to before me, this 27th day of March, 1967.

*Ronnie Donnelly*  
Ronnie Donnelly - Notary Public

My commission expires:

February 15, 1971