

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rice County, Sec. 33 Twp. 20 Rge. 8 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C E 1/2 NE NW

Lease Owner Thomas A. Allan

Lease Name Shaffer Well No. 1

Office Address R. R. #1 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed 11-16-66 19__

Application for plugging approved 11-17-66 19__


Plugging commenced 12-2-66 19__

Plugging completed 12-14-66 19__

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3310 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	TO	SIZE	PUT IN	PULLED OUT
			8 5/8	187	None
			5 1/2	None	2019

RECEIVED
DEC 19 1966
CONSERVATION DIVISION
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Rigged up.

Cleaned out cellar. Sanded to 3265'. Dumped 5 sacks of cement. Working pipe. Shot pipe at 2611'.

Loaded hole with water. Shot pipe at 2514'. Working pipe - had 16" tension at 27 joints.

Pumped out 33 bbls of water - no pressure. Pumped out one load.

Spotted oil. Pumped 33 more bbls of oil and 132 bbls of water pushing plug to 2414'. Pressure at 600# broke to 325#.

Working pipe. Shot pipe at 2300' - 2100' and 2010'. Pulling pipe.

Plugging well. Bailed hole to 185' rock bridge with 20 sacks. Build mud rock bridge from 40' to 30' with 10 sacks. Capped well with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of December 19 66

My commission expires May 27, 1969

[Signature]
Notary Public.

15. 159. 05034. 0000

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY BRUNSON DRILLING CO ET AL


SEC. 33 T. 20 R. 8W
LOC. CE 1/2 NE NW

FARM Schaffer Est. NO. 1

TOTAL DEPTH 3310
COMM. 12- 9-50
SHOT OR TREATED
CONTRACTOR
ISSUED - 2-3-51

COMP. 12-20-50

COUNTY Rice



CASING
8 5/8" 187'
5 1/2" 3280'

ELEVATION 1665 R.B.

PRODUCTION 5,600,000 gas

surface soil	8
sand & gravel	170
red bed & shale	340
anhyd.	365
red beds	550
shale	855
salt	940
salt & shale	1070
lime brkn	1215
lime	1720
lime & shale	2035
shale	2325
shale & lime	2635
lime brkn	2745
lime	2850
lime & shale	2960
lime	3136
lime & shale	3282
congl. & shale	3298
congl.	3310
Total Depth	

FIGURED INDICATE BOTTOM OF FORMATIONS

Tops:	
Brown lime	2868
Lansing	2884
Soc'y chert	3278