

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

BARTON County, Sec. 10 Twp. 20s Rge. 12 (W)

Location as "NE/CNW/SW" or footage from lines. APP. SE NW NW
Lease Owner. PETROLEUM, INC.,
Lease Name STRONG Well No. B-1
Office Address R. R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JANUARY 10 19 69
Application for plugging filed JANUARY 10 19 69
Application for plugging approved JANUARY 10 19 69
Plugging commenced JANUARY 10 19 69
Plugging completed JANUARY 10 19 69
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production. NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3428 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	209'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

HEAVY MUD TO 500', FOLLOWED BY WOODEN PLUG, PLACED 25 SACKS CEMENT ON TOP OF PLUG.
HEAVY MUD TO 200', FOLLOWED BY WOODEN PLUG, PLACED 20 SACKS CEMENT ON TOP OF PLUG.
HEAVY MUD TO 40', FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACK HULLS AND 10 SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
Address R. R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD, DIST. PROD. SUPT. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*
R. R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of JANUARY, 19 69

My commission expires MAY 28, 1969: *Richard H. Dumber* Notary Public.

WELL LOG

15.009.20338,0000

COMPANY Petroleum, Inc.

SEC. 10 T. 20S. R. 12W

FARM Strong NO. B-1


LOC. SE NW NW

TOTAL DEPTH 3428'

COUNTY Barton County, Kansas

COMM. 1-2-69 COMP. 1-10-69

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 209' w/250 sx

ELEVATION 1813' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

96' Sand
 105' Hard Sand
 209' Blue Shale
 280' Sand & Shale
 610' Red Bed
 618' Anhydrite
 1370' Shale & Shells
 3208' Lime & Shale
 3375' Lime
 3408' Lime & Shale
 3428' Arbuckle
 3428' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 17 1969
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas }
 County of Barton } ss

I, Eunice McEachern of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Strong B-1 well.

Eunice McEachern

Subscribed and sworn to before me this 13th day of January 1969

My Commission Expires: November 5th, 1969

Richard Doy
 NOTARY PUBLIC