

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas


15.009.05238.0000

WELL PLUGGING RECORD

Barton County. Sec. 10 Twp. 20 Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE
Lease Owner Francis Oil and Gas, Inc.
Lease Name Hood Well No. 2
Office Address 905 Palace Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-23-59 19
Application for plugging filed 9-23-59 19
Application for plugging approved 9-23-59 19
Plugging commenced 9-23-59 19
Plugging completed 9-23-59 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3399 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	280'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set @ 270' w/ 25 sx. cement & 1/4 sx. hulls.
Top plug set @ 40' w/ 10 sx. cement & 1/4 sx. hulls.

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September 19 59

My commission expires April 23, 1963

Juanita M. Green Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

DRILLER'S LOG

OCT 1 1959

CONSERVATION DIVISION
Wichita, Kansas

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

COMMENCED:
COMPLETED:

FRANCIS OIL AND GAS, INC.
LEBEN DRILLING, INC.
HOOD #2
NW NE NE SECTION 10-20-12W
BARTON COUNTY, KANSAS
9-15-59
9-23-59

0	120	Sand
120	125	Sand
125	130	Iron
130	150	Sand
150	202	Blue Shale
202	309	Shale
309	560	Redbed
560	595	Redbed
595	635	Anhydrite
635	1290	Redbed, Shale and Shells
1290	1500	Shale and Shells
1500	1855	Lime and Shale
1855	2000	Lime, Shale and Salt
2000	2275	Shale and Lime
2275	2640	Shale and Lime
2640	2795	Lime and Shale
2795	2935	Lime
2935	3155	Lime and Shale
3155	3360	Lime
3360	3399	Lime
	<u>3399</u>	<u>Rotary Total Depth - D & A</u>

Set 8 5/8" surface casing @ 200' with 200 sacks H. A. 5 cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Hood #2, located NW NE NE of Section 10, Township 20 South, Range 12 West, Barton County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin

Frank Hamlin

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 29th day of September, 1959.

Juanita M. Green

Juanita M. Green, Notary Public

My Commission Expires:
April 23, 1963