


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 6 Twp. 20 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SE NW

Lease Owner David Fransen

Lease Name Fransen Well No. 2

Office Address 145 S. Pershing, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 22, 19 55

Application for plugging filed September 22, 19 55

Application for plugging approved September 22, 19 55

Plugging commenced September 22, 19 55

Plugging completed September 22, 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Warren Horner

Producing formation Depth to top Bottom Total Depth of Well 3510 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.
Set bottom plug at 300' with
20 sacks cement. Filled hole
to 35' and set top plug with
10 sacks cement circulated to
surface.

9-23-55

RECEIVED RECEIVED
STATE CORPORATION COMMISSION STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Sterling Drilling Company
Address Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
Sterling, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 1955

My commission expires My Commission Expires Jan. 22, 1958 Notary Public.

PLUGGING
FILE SEC 6 T 20 R 12 W
BOOK PAGE 2 LINE 41

STERLING DRILLING CO.

STERLING, KANSAS

WELL LOG-----FRANSEN #2

Location: SW SE NW, Section 6-20S-12W,
Barton County, Kansas

OWNER: David Fransen

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 9-12-55

COMPLETED: 9-22-55

TOTAL DEPTH: 3510'

LOG

0-110	Surface Soil & Sand
110-120	Iron
120-130	Pyrite
130-320	Sand & Shale
320-420	Red Bed
420-955	Shale, Shells & Red Bed
955-985	Anhydrite
985-1400	Shale
1400-2355	Limestone & Shale
2355-2555	Shale & Shells
2555-2685	Shale
2685-2765	Limestone & Shale
2765-2975	Limestone
2975-3185	Shale & Limestone
3185-3375	Limestone
3375-3435	Limestone & Shale
3435-3490	Chert & Limestone
3490-3510	Limestone T.D.

CASING RECORDSet 8-5/8" casing at 320' with 175
sacks cement.PRODUCTION

Plugged & Abandoned

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1955

CONSERVATION DIVISION
Wichita, Kansas