


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rice County, Sec. 3 Twp. 20 Rge. 9 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SW NW
Lease Owner Robin Supply Corp.
Lease Name Bohrer Well No. #1
Office Address 1322 East 50th, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-8-65 19
Application for plugging filed 6-8-65 19
Application for plugging approved 6-8-65 19
Plugging commenced 6-8-65 19
Plugging completed 6-8-65 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Toman
Producing formation Depth to top Bottom Total Depth of Well 3298 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	231	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 220 feet. Set plug at 220. Run 25 sacks cement set plug and Halls at 40'. Run 10 sacks cement put 2 sacks cement in Rat Hole.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Mast Drilling, Inc.
Address Box 33, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Louis M. Mai

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 33, Russell, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 15th day of June 1965

My commission expires

11-9-67

Delphin A. Becker

Notary Public.

WELL LOG

OPERATOR: Robin Supply Corp.
1322 East 50th
Tulsa, Oklahoma

CONTRACTOR: Mast Drilling, Inc.
Box 33
Russell, Kansas

LEASE: Bohrer #1
SE SW NW
Section 3, T-20, R-9
Rice County, Kansas

COMMENCED: 6-3-65

COMPLETED: 6-8-65

CASING: Run 8 5/8" Surface Pipe
@ 231'. Cemented w/175
sacks cement. Cement
circulated to top.

FORMATION	DEPTH
Clay & Sand	75
Shale & Sand	140
Red Bed	233
Red Bed, Shale	299
Anhydrite	320
Red Bed, Shale & Shells	1025
Shale & Shells	1125
Shale & Lime	2480
Lime	3015
(Topeka	2455)
(Douglas	2759)
(Heebner	2729)
(Brown Lime	2860)
(Toronto	2750)
(Lansing K.C.	2886)
Lime	3200
Lime, Chale, Conglomerate	3266
Conglomerate	3289
Arbuckle	3298
TOTAL DEPTH	3298

STATE OF KANSAS)

)SS

RUSSELL COUNTY)

I hereby certify that the above information is true and correct
to the best of my knowledge.

Louis M. Mai

Louis M. Mai
President

Subscribed and sworn to before me this 15th day of June, 1965.

Delphin A. Becker

Delphin A. Becker
Notary Public

My commission expires: 11-9-67