


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.



Locate well correctly on above  
Section Flat

Rice County, Sec. 3 Twp. 20S. Rge. 9(W)  
Location as "NE1/4NW1/4SW1/4" or footage from lines C, S/2, SE/4, SW/4  
Lease Owner The Bay Petroleum Corporation  
Lease Name Keesling Well No. 1  
Office Address Box 957 Denver Colorado.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed Dec. 7 1940  
Application for plugging filed April 1 1947  
Application for plugging approved April 3 1947  
Plugging commenced April 25 1947  
Plugging completed April 29 1947  
Reason for abandonment of well or producing formation Failure to produce in  
quantity sufficient to warrant continued operation.  
If a producing well is abandoned, date of last production March 10 1947  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee  
Producing formation Arbuckle Depth to top 3209' Bottom 3224' Total Depth of Well 3224' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	215'	None
				5 1/2"	3215'	2631'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Ran 6 sax cement to bottom of hole,  
Mudded hole to 175',  
Set bridge and ran 15 sax cement,  
Mudded hole and ran 5 sax cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Bay Petroleum Corporation,  
Address Box 513, Chase, Kansas.

STATE OF Kansas, COUNTY OF Rice, ss:  
Forrest Crawford (employee of owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Forrest Crawford  
(Address)

SUBSCRIBED AND SWORN to before me this 3 day of May, 1947  
Vincent O. Gray Notary Public.

My commission expires May 20, 1950

PLUGGING  
FILE SEC 3 T20 R9W  
BOOK PAGE 105 LINE 5

WELL DOG BUREAU \* KANSAS GEOLOGICAL SOCIETY  
412 Union National Bank Bldg, Wichita, Kans.

Bay Petroleum Corporation  
Comm. 11-20-40. Comp. 12-3-40.  
S. Keesling 1

Sec. 3 T. 20S R. 9W  
CSL SE SW  
330 'fsl 660' fel SW/4

Total Depth. 3224'  
Shot or treated.  
Contractor  
Issued. 1-25-41.

County. Rice.

Elevation . 1698

CASING.  
8 5/8" 215'  
5 1/2" 3215'

Production Pot. 450.26 B

Figures Indicate Bottom Of Formations.

sand and shale	100	shale	2810
shale	185	lime	2825
shale and shells	250	shale	2886
red rock	575	lime	3172
shale and shells	820	shale	3205
shale salt	1030	conglomerate	3207
shale and shells	1490	shale Simpson	3209
lime broken	1565	chert and dolomite	3224
lime and shale	1730	Total Depth.	3224
lime	1760		
lime and shale	1860	<u>Tops.</u>	
lime	1890	Lansing Kansas City	2883
shale shells	2060	Conglomerate	3203
shale	2175	Simpson	3207
shale and lime	2250	Arbuckle	3209
shale and shells	2365		
lime	2405		
shale and lime	2475		
shale and shells	2485		
lime	2765		

**PLUGGING**

FILE SEC-3 T-20 R-9W  
BOOK PAGE 105 LINE 5

