

STATE OF KANSAS
STATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-159-19013-00-00
API NUMBER Drilled 1944

RECEIVED
OCT 22 2002
KCC WICHITA

10-22-02
TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR DON FOX
ADDRESS P.O. Box 466 Chase, Kansas 67524

PHONE (620) 662-2862 OPERATORS LICENSE NO. 7079

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3735'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	184'	None
				5-1/2"	3217'	None
				4-1/2" Liner	195'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each side. Perforated well @2600', 1150', 750' & 250'. Ran 1" tubing to 2600', pumped 60 sacks cement, pulled tubing to 1150', pumped 40 sacks cement, pulled to 750', pumped 40 sacks cement, pulled up to 250' and circulated 60 sacks cement to surface. Pulled 1" tubing out, welded 5-1/2" collar on to long-string, pumped 60 sacks cement down 5-1/2" casing & circulated up 8-5/8" surface. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529
Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Don Fox

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 467 - Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of October, 2002

[Signature]
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05

Form CP
Revised 05-

[Initials]