

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rice County. Sec. 3 Twp. 20 Rge. 9 (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines. C, S/2, SW/4, SW/4.

Lease Owner The Bay Petroleum Corporation,

Lease Name Mitchell Well No. 1

Office Address Box 957, Denver, Colorado.

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed Dec. 17 1940

Application for plugging filed April 1 1947

Application for plugging approved April 3 1947

Plugging commenced May 2 1947

Plugging completed May 2 1947

Reason for abandonment of well or producing formation Failure to produce oil.

If a producing well is abandoned, date of last production October 1945

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee.

Producing formation Arbuckle Lime Depth to top 3236 Bottom 3244 Total Depth of Well 3244 Feet

Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	220'	None
				5 1/2"	3236'	2672' 5"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran 6 sax cement to bottom of hole.
Mudded hole to 200'.
Set bridge and ran 15 sax cement.
Mudded hole and ran 5 sax cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Bay Petroleum Corporation,
Address Box 513, Chase, Kansas.

STATE OF Kansas COUNTY OF Rice
Forrest Crawford (employee of owner) or owner or operator of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Forrest Crawford

(Address)

SUBSCRIBED AND SWORN to before me this 8 day of May 10 1947 1947

My commission expires May 20, 1950

PLUGGING
FILE SEC 3 T 20 R 9 W
BOOK PAGE 105 LINE 7

15.159.04752.0000

BAY PETRO. CORP.
Mitchell No. 1.

Sec. 3 T. 20 R. 9W.
CSL SW SW
660' fr WL. 330' fr SL SW/4

Total Depth. 3224'
Comm. 12-4-40 Comp. 12-17-40
Shot or treated.
Contractor.
Issued. 1-25-41.

County - Rice.

CASING:
8 1/2" 220'
5 1/2" 3236' 5".

Elevation - 1703.
Prod. pot. 454.24 B.

Figures Indicate bottom of formations.

Surface	10
shale	30
sand	192
shale & shells	240
red rock	590
shale & shells	820
shale & salt	1040
shale & shells	1180
anhydrite	1205
shale & shells	1270
shale & lime	1380
lime shells & shale	1490
shale & lime	1670
lime shells & shale	1795
shale & shells	1855
lime	1885
shale & shells	2175
lime	2210
shale & shells	2335
lime	2360
shale & shells	2506
lime	2760
shale	2775
shale & shells	2889
lime	3175
shale	3219
shale	3236
Lime Arbuckle	3244
Total Depth.	
Top Arbuckle	3236'

MAY 10 1947

PLUGGING
FILE SEC. 3 T. 20 R. 9W
BOOK PAGE 105 LINE 7