

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
off formations.

Rice County. Sec. 2 Twp. 20 Rge. 9 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE-SW-SW

Lease Owner John Lindas, et. al.

Lease Name Darling Well No. 1

Office Address 1316 Union National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 2-20-48 19.

Application for plugging filed 2-20-48 19.

Application for plugging approved 2-20-48 19.

Plugging commenced 2-20-48 19.

Plugging completed 2-20-48 19.

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 2965 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				12 $\frac{1}{2}$ "	118'	None
				7"	2915'	2700' approx.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Chat and mud - 2965' to 2915' 5 sacks cement at 2915' Heavy mud 2915' to 120'  
20 sacks cement at 120' Heavy mud 120' to 15' 10 sacks cement to surface.

JUN 5 1948  
6-8-48

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lindas Oil, Inc.  
Address 1316 Union National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Scott Stuckey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) BY: Scott Stuckey  
LINDAS OIL, INC.


(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of June 1948

My commission expires March 25, 1952

Catherine Darcy  
Notary Public.

My commission expires



February 22, 1948  
DRILLING LOG

Lindas Oil, Inc. et. al.  
1316 Union National Bank Building  
Wichita, Kansas

Lease: Darling #1

County: Rice, Kansas  
Section: 2-20-9W  
Location: NE-SW-SW

Rotary Total Depth: 2965'  
Comm: 12-24-47 Comp: 2-20-48  
Shot or Treated  
Casing: 12 1/2" @ 118' 7" @ 2915'

Contractor: Gabbert & Lindas Drilling Company, Inc.  
1316 Union National Bank Building  
Wichita, Kansas

Figures Indicate Bottom of Formation:

0	to	8	Cellar
8		15	Clay
15		44	Sand
44		105	Shale & sand
105		125	Shale & shells
125		135	Sand & gravel
135		262	Red bed & shale
262		272	Amphidrite
272		515	Shale & shells
515		1065	Shale & salt
1065		1115	Shale & shells
1115		1170	Lime broken
1170		1845	Lime
1845		2445	Lime & shale
2445		2740	Lime
2740		2825	Shale & shells
2825		2870	Shale with Lime streaks
2870		2872	Shale
2872		2927	Lime
2927		2941	Shale
2941		2946	Shale - Lime & shells
2946		2963	Lime soft
2963		2965	TD Lime hard



STATE OF KANSAS )  
                          ) SS:  
COUNTY OF SEDGWICK )

I, the undersigned, being duly sworn on oath state that the above statement and log is true and correct record and log of the well drilled at the location above described.

GABBERT & LINDAS DRILLING COMPANY, INC.

By: Scott Shuckey

Subscribed and sworn to before me this 7 day of June, 1948

Catherine Dancy  
Notary Public

My commission expires March 25, 1952

**PLUGGING**  
FILE SEC 2-70 R9W  
BOOK PAGE 29 LINE 1