

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-159-21,203-0000

LEASE NAME Father Flanagan

WELL NUMBER A-2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 2 TWP. 20s RGE. 9W (E) or (W)

COUNTY Rice

Date Well Completed

Plugging Commenced 11-07-96

Plugging Completed 11-08-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Clinton Production, Inc.

ADDRESS 330 N. Armour Wichita, KS 67206

PHONE#(316) 684-7996 OPERATORS LICENSE NO.

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Jack Luthie (XCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3378'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	234'	none
				4 1/2	3373.50'	2404'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Plugged off bottom with sand to 2870' & 4 sks cement. Shot at 2404', pipe came free. Pulled to 1150', pumped 35 sks cement. Pulled to 750', pumped 35 sks cement. Pulled to 300', circulated cement to surface w/100 sks. Pulled rest of pipe. Topped off. Plugging complete 60/40 4%.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Clinton Production, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

11-13-96
 RECEIVED
 KANSAS CORP COM
 NOV 12 1996
 SUBSCRIBED AND SWORN TO before me this 12th day of November, 1996
 Commission Expires:

Jane Bergberg
 Notary Public

