

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

660'S. - 330'E.

of N.W. corner of

Well Location N. E. Sec. 33 Twp. 20-S. Rge. 10 (X) (W)Field Name (if any) Raymond County RiceLease (Farm Name) Nellie Beaman Well No. 1Was well log filed with application? no If not, explain circumstances

and give available data (Use an additional sheet if necessary)

10 3/4" O.D. Casing set at 260'. Cemented with 120 sacks of regular
and 30 sacks of Encore quick set cement. Drilled to a T. D. of 3345'
Arbuckle Lime. Top of Arbuckle 3327. This proved to run low and non-
productive. Top of Lansing 2983'. A zone of saturation was encountered
from 3061' to 3071'. 5 1/2" O.D. casing set and cemented with 125 sacks of
cement at 3108', leaving shoe jt. (3316") full of cement. This was not
drilled out. Casing perforated with 48 shots from 3061 to 3073. (see attached)
Date and hour plugging is desired to begin 1 - 16 - 1942.

Plugging of the well will be done in accordance with the Rules and Regu-
lations of the State Corporation Commission, or with the approval of
the following exceptions: Explain fully any exceptions desires (Use an
additional sheet if necessary) No exemptions requested.

General method of plugging.Name of the person on the lease in charge of well for owner Gage W. LeeSup't. Address 401 S. Purdy Street Lyons, Kansas.Name of well owner or Acting Agent Gilbert C. MooreAddress 606 Union National Bank Building Wichita, Kansas.

Invoice covering assessment for plugging this well should be sent to:

Luther Mackall Address 606 Union Nat'l. Bank Bld'g, Wichita,
Kansas.

and payment will be guaranteed by applicant.

Luther Mackall
Gilbert C. Moore
Operator or Acting Agent

Date Jan 15, 1942 1-20-1942

33-20-10W
22-1-1

-----SUPPLEMENT TO WELL PLUGGING APPLICATION-----

After well was perforated, a very light show of free oil was encountered. Well was treated with a 500 gallon Acid clean up treatment, 1000 gallons Acid under pressure. After 24 hours testing well bailed 25 gallons of oil and 25 gallons water. The $5\frac{1}{2}$ " O.D. casing was ripped from 3061 to 3071, ripping two separate slots this length. No noticable increase of oil, gas or water showing. Well was then acidized with 6000 gallons of acid. After 48 hours of swabbing, bailing and testing well finally finished up making $1\frac{1}{4}$ barrel of oil and $1\frac{1}{2}$ barrels of water.

LUTHER MACKALL
OIL PRODUCERS
UNION NATIONAL BANK BUILDING
WICHITA, KANSAS

January 19, 1942.

State Corporation Commission,
Conservation Division,
800 Bitting Building,
Wichita, Kansas.

Gentlemen:

Enclosed please find Well Plugging
Application on the Nellie Beaman No. 1,
and certified Well Log certified by
Mr. J. L. Carey of the Rocket Drilling
Company.

Send your charge for plugging to
Luther Mackall, 606 Union National Bank
Building, Wichita, Kansas.



Yours very truly,

LUTHER MACKALL,

SS:S
Enclosure

By

Scott Hickey





15.159.03168.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

January 21, 1942

IN REPLY PLEASE
REFER TO THIS
SUBJECT

Well No. 1
Farm Nellie Boaman
Description NW 33-26-10W
County Rice
File 22-1

Mr. Luther Mackall
606 Union National Bank Bldg.
Wichita, Kansas

Dear Sir:

This letter is your permit to plug
the above subject well, in accordance
with the Rules and Regulations of the
STATE CORPORATION COMMISSION.

Yours very truly,

STATE CORPORATION COMMISSION

T. A. MORGAN, DIRECTOR
CONSERVATION DIVISION

HA

BY: J. P. Roberts
J. P. ROBERTS

NOTICE: Ruel Durkee
McPherson, Kansas