

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 63-4LOCATION NW-NE SE SWSEC. 9-16 TWP. 20 RGE. 11-WDry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:


Well No. 1 Lease M. GreelofOperator Standard Oil & Gas Co Address Box #7 - Okinwood - Kans.Field County BartonTotal Depth 3312 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 1/2" - 209 ft - Circulated with cement.
7" casing set at 3288 ft - Filled back from bottom
& 3288 ft with chat - Dumped 5 sacks of cement at
3288 ft - Shot off & Pulled the 7" casing - Filled with
mud to 209 ft - Set back Bridge & 20 sacks of cement
at 209 ft - Mud to 20 ft from the surface - Plug &
10 sacks of cement at the surface

RECEIVED

Conservation Div.

C. M. Stough -
District Conservation AgentDate 2-6-49

STANOLIND OIL AND GAS COMPANY

Ellinwood, Kansas
January 17, 1949

File: HGN-85-87.1

Subject: Well No. 1
M. Gerlof Lease
Barton County, Kansas

Mr. J. P. Roberts
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Dear Sir:

Please refer to your letter dated January 15th, regarding the above subject in which you requested information regarding the status of our M. Gerlof Well No. 1.

To date, we have not plugged this well but intend to do so within the very near future.

*16-80-11W
Barton, K.*

LGD/vmc

Very truly yours,

H. G. Nething
H. G. Nething
Field Superintendent

RECEIVED

Conservation Div.

JAN 18 1949

STATE CORPORATION
COMMISSION
KANSAS

Nº K68131

DATE October 20, 1948

ORDERED FROM

ADDRESS

RENDER INVOICE IN DUPLICATE FOR EACH ORDER, SHOW ORDER NUMBER ON ALL COPIES OF INVOICE AND MAIL TO

STANOLIND OIL AND GAS COMPANY

CITY

STATE

[illegible]**CHARGE TO****USED FOR**

TERMS

STANOLIND OIL AND GAS COMPANY

By acceptance of this order, Seller represents that the sale of the article or articles referred to herein, and the price therefor and delivery thereof will conform to all applicable federal and state laws, orders, rules and regulations.

三