

STATE OF KANSAS  
STATE CORPORATION COMMISSION,  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

## WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rice SEC. 2 TWP. 20s RGE. 10w E/W  
Location as in quarters or footage from lines:  
80' N of NW - NW/4


Lease Owner Gable Oil CompanyLease Name Sieker #2

Well No. \_\_\_\_\_

Office Address Box 166, Chase, Kansas 67524

Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_

Date Well Completed \_\_\_\_\_

Application for plugging filed \_\_\_\_\_

Plugging commenced 12/4/82Plugging completed 12/17/82

Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert TomanProducing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3345'

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	266'	none
				5 1/2"	3344'	2663'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged bottom with sand to 2990', set 5 sacks cement, Shot pipe at 2684' Layed down 77 joints. Mixed 5 hulls, 7 gel, Blew out side of surface pipe 4' down. Ran 600' tubing, pumped in 6 gel, pulled tubing to 300'. Circulated cement to surface with 200 sacks 50/50 pos, 2% gel.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing PullingSTATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell KelsoBox 347, Chase, Ks. 67524

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December, 1982

My Commission expires:



RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public

DEC 30 1982

CONSERVATION DIVISION  
Wichita, Kansas

15.159.21044.0001

Phone 913-483-2627, Russell, Kansas

Phone Plainville: 913-434-2812

Phone 316-793-5861, Great Bend, Kansas

Phone Kiowa 316-825-4618

**ALLIED CEMENTING CO., INC.** No. 34810

Home Office P. O. Box 31

Russell, Kansas 67665

Date 12-16-82 Sec.    Twp.    Range    Called Out 6:00 AM On Location 1045 Job Start 11:15 Finish 12:00  
 Lease Secret Well No. #2 Location BT RC CL 4E/4S County Rice State KAN

Contractor Kelso  
 Type Job Old Hole Plug  
 Hole Size 7 3/4 T.D. 3345  
 Csg. Size 5 1/2 Depth     
 Tbg. Size    Depth     
 Drill Pipe    Depth     
 Tool    Depth     
 Cement Left in Csg.    Shoe Joint     
 Press Max. 800 Minimum     
 Meas Line    Displace   

Perf.     
**EQUIPMENT**  

Pumptrk	No. <u>63</u>	Cementer	<u>PRATON</u>
		Helper	<u>KIRK</u>
Pumptrk	No. <u>  </u>	Cementer	<u>  </u>
		Helper	<u>  </u>
Bulktrk	<u>96</u>	Driver	<u>MARK</u>
Bulktrk	<u>  </u>	Driver	<u>  </u>

DEPTH of Job     
 Reference: Pump Truck 155-30  
Plus 40-00  
WC  
 Sub Total     
 Tax     
 Total   

Remarks: Mixed 5 holls  
**RECEIVED**  
 STATE COMMISSION 7966 Blow out side of surface pipe  
4' down -  
**JAN 07 1983**  
 CONSERVATION DIVISION  
 Wichita, Kansas

Owner  
 To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish  
 cementer and helper to assist owner or contractor to do work as listed.  
 Charge To Gable Wall Sealing  
 Street HY 56-96 WEST  
 City CHASE State KAN 67524  
 The above was done to satisfaction and supervision of owner agent or  
 contractor.

Purchase Order No. X. P. S. to Allied  
**CEMENT**

Amount Ordered 100.50 Total 3.00  
 Consisting of 279d 5 holls  

Common	<u>50</u>	<u>5.00</u>
Poz. Mix	<u>50</u>	<u>2.00</u>
Gel.	<u>277</u>	<u>7.75</u>
Chloride	<u>2</u>	<u>2.00</u>
Quickset	<u>5</u>	<u>14.00</u>
		<u>70.00</u>

Sales Tax     
 Handling 12 90 10.80  
 Mileage - Min 66 40.00  
 Sub Total     
 Total 171.55

Floating Equipment     
THANK YOU.

15.159.21044.0001

Phone 913-483-2627, Russell, Kansas

Phone Plainville 913-434-2812

Phone 316-793-5861, Great Bend, Kansas

Phone Kiowa 316-825-4618

**ALLIED CEMENTING CO., INC.** No 34872

Home Office P. O. Box 31

Russell, Kansas 67665

010  
 Date 12-17-82 Sec. Twp. Range Called Out 9:00am On Location 12:35pm Job Start 3:00pm  
 Lease Secret Well No. Location 56 + Raymond Rd. 1E side County Rice State Ks

Contractor Gable WellType Job Plug to AbandonHole Size 8 7/8 T.D.

Csg. Size Depth

Tbg. Size 2 3/4 Depth 499ft.

Drill Pipe Depth

Tool Depth

Cement Left in Csg. Shoe Joint

Press Max. Minimum

Meas Line Displace

Perf.

**EQUIPMENT**

Pumptrk	No	Cementer	<u>Curtis Russell</u>
	<u>158</u>	Helper	
Pumptrk	No	Cementer	<u>Ken P</u>
		Helper	
Bulktrk		Driver	
	<u>116</u>	Driver	

**DEPTH of Job**

Reference:	<u>pump Trk only</u>	<u>340<sup>00</sup></u>
	<u>16 pump Trk mileage</u>	<u>16<sup>00</sup></u>
	Sub Total	
	Tax	
	Total	<u>356<sup>00</sup></u>

**Remarks:**

mixed 6 1/2 Gel @ 499ft. mixed 50/50 @ 312ft until cement  
circulated, capped with bag of cement

**Owner**

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish  
 cementer and helper to assist owner or contractor to do work as listed.

**Charge To**Gable Well Service**Street**Box 166**City**Chase**State**Ks 67524

The above was done to satisfaction and supervision of owner agent or contractor.

**Purchase Order No.****CEMENT****Amount**Ordered 100 21 50/50 2 1/2 3 1/2 6 1/2 inside**Consisting of**

Common	<u>50 21 @ 5<sup>00</sup></u>	<u>250<sup>00</sup></u>
Poz. Mix	<u>50 21 @ 2<sup>10</sup></u>	<u>105<sup>00</sup></u>
Gel.	<u>8 21 @ 7<sup>25</sup></u>	<u>58<sup>00</sup></u>
Chloride	<u>3 21 @ 20<sup>00</sup></u>	<u>60<sup>00</sup></u>
Quickset		

473<sup>00</sup>**Sales Tax****Handling**111 21 @ 90<sup>00</sup>**Mileage**16 miles @ 66<sup>00</sup>**Sub Total****Total****Floating Equipment**Thank You