


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 11 Twp. 20S Rge. 12W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SE NW
Lease Owner Alpine O. I. & Royalty Co., Inc. et al
Lease Name Woodmansee Well No. 1-D
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed December 17, 1960 19
Application for plugging filed December 17, 1960 19
Application for plugging approved December 17, 1960 19
Plugging commenced December 17, 1960 19
Plugging completed December 18, 1960 at 2:30 A. M. 19
Reason for abandonment of well or producing formation non-productive in
commercial quantities
If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Tolman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3390 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	102'	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from 3390 feet to 150 feet - Placed 10' log with Retainer's attached Halliburton plug nailed to top plus 2 folded hull sacks and 10 feet of rock on top for bridging. Then 25 sacks cement ~~XXXXXX~~ through drill pipe. Mud to 40 feet - 1/4th sack hulls and plug with 10 sacks cement to base celler. Filled rat hole to 8 feet and 2 sacks cement.

STATE CORPORATION COMMISSION

DEC 29 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December 1960

My commission expires August 10, 1961
Notary Public.

R

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: December 8, 1960

Contractor: Quaker Drilling Co., Inc.

Completed: December 17, 1960

Woodmansee No. 1-D
SW SE NW Sec. 11-20S-12W
Barton County, Kansas

Elevation: 1799 K. B.

Production: D. & A.

Casing Record:

Set 8 5/8 inch casing at 102 feet with 175 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Sand	96	Heebner	2979 -1180
Hard Sand	102	Brown Lime	3102 -1303
Very Hard Sand	107	Lansing	3120 -1321
Blue Shale	130	Base of Kans. City	3353 -1554
Shale, Red Bed & Sand	575	Arbuckle	3361 -1562
Anhydrite	605	Rotary Total Depth	3390 -1591
Red Bed, Shale & Shells	930		
Shale and Shells	1490		
Lime and Shale	1835		
Sandy Lime and Shale	1890		
Shale and Shells	2505		
Shale and Lime	3075		
Lime	3170		
Lime and Shale	3191		
Lime	3361		
Dolomite	3390		


RECEIVED
STATE COMMISSION
DEC 29 1960
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SW SE NW of Section 11, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: 
Dwight J. Wilson

SUBSCRIBED AND SWORN TO BEFORE ME a Notary Public this 28th day of December, 1960.


Virginia Mandell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1961