


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas



Locate well correctly on above
Section Plat

/ Barton County, Sec. 11 Twp. 20S Rge. 12W(E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name WOODMANSEE "C" Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed July 1, 1959 19
Application for plugging filed July 3, 1959 19
Application for plugging approved July 6, 1959 19
Plugging commenced July 7, 1959 19
Plugging completed July 9, 1959 19
Reason for abandonment of well or producing formation non-producing in
commercial quantities
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3420 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	170'	Cemented
				5 1/2	3353	2702.69'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand 3420' to 3340'
Cement 3340' to 3315'
Mud 3315' to 180'
Rock 180' to 170'
Cement 170' to 95'
Mud 95' to 40'
Rock 40' to 30'
Cement 30' to 0'

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pipe Pulling Company
Address Box 114 - Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Thomas M. McCaul*
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of July, 19 59

My commission expires August 10, 1961

Virginia Mendell
Notary Public.

PLUGGING
FILE SEC. 11 T. 20 R. 12W
BOOK PAGE 48 LINE 44

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: June 5, 1959

Contractor: Quaker Drilling Co., Inc.

Completed: June 13, 1959

Woodmansee "C" No. 1
NE NE SE Sec. 11-20S-12W
Barton County, Kansas

Elevation: 1797 KB

CASING RECORD

Set 8 5/8 inch casing at 170 feet with 175 sacks cement
Set 5 1/2 inch casing at 3353 feet with 125 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>
Sand	90	Heebner 2968 -1171
Shale	170	Brown Lime 3069 -1292
Shale and Sand	300	Lansing 3107 -1310
Red Bed	554	Base of Kansas City 3340 -1543
Anhydrite	582	Arbuckle 3351 -1554
Shale	910	Rotary Total Depth 3361 -1564
Shale and Shells	1275	
Lime and Shale	1453	
Shale and Lime	1595	
Sandy Lime and Shale	1750	
Lime and Shale	1970	
Shale and Shells	2620	
Lime and Shale	2965	
Shale	3040	
Lime and Shale	3119	
Lime	3265	
Lime and Shale	3285	
Lime	3351	
Dolomite	3361	

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NE NE SE of Section 11, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: 

Thomas M. McCaul, President

SUBSCRIBED AND SWORN to before me a Notary Public this 16th day of June, 1959.


Virginia Mandell, Notary PublicMY COMMISSION EXPIRES:
August 10, 1961