

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Bldg  
Wichita, Kansas

Barton

County, Sec. 11 Twp. 20 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines SE  $\frac{1}{4}$  SE  $\frac{1}{4}$  SW  $\frac{1}{4}$

Lease Owner Heathman-Seeligson

Lease Name Steckel

Well No. 1

Office Address 254 N. Washington, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-13-1953

Application for plugging filed 11-13-1953

Application for plugging approved 11-13-1953

Plugging commenced 11-13-1953

Plugging completed 11-13-1953

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	160'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 160' with 1/2 Sx Hulls and 15 Sx Cement.  
Heavy mud up to 40', top plug @ 10 Sx Cement @ 40'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company

Address 607 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
L. L. Bailey

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. L. Bailey

607 Union National Bank Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 19 53

Arthur R. Derrington

Notary Public.

My commission expires August 20, 1956

PLUGGING  
FILE SEC 11 T 20 R 120  
BOOK PAGE 43 LINE 15

24-7368-5 3-53-20M

11-18-1953

## WELL LOG

15.009.01393.0000

COMPANY Heathman-Seeligson

SEC. 11 T. 20 R. 12W

FARM Steckel

NO. 1.

LOG. SE $\frac{1}{4}$  SE $\frac{1}{4}$  SW $\frac{1}{4}$ 

TOTAL DEPTH 3490'


COMM. 10-31-53

COMP. 11-13-53

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

COUNTY Barton  
KANSAS

CASING


20	10
15	8-5/8" 160'
12	6
13	5

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	125	Sand
125 -	160	Blue Shale
160 -	460	Shale & Red Bed
460 -	585	Shale & Shells
585 -	620	Anhydrite
620 -	1285	Shale & Shells
1285 -	1420	Shale
1420 -	1555	Shale, Sand, Lime Stks
1555 -	2095	Lime & Shale
2095 -	2265	Shale & Shells
2265 -	2565	Shale & Lime
2565 -	2740	Shale
2740 -	2835	Broken Lime
2835 -	2965	Lime
2965 -	3085	Lime & Shale
3085 -	3104	Shale
3104 -	3360	Lime
3360 -	3490	Conglomerate
3490 -	TD	

RECEIVED  
STATE CORPORATION COMMISSION

NOV 18 1953

CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS

County of SEDGWICK

SS:

I, L. L. Bailey of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Steckel #1 well.

Subscribed and sworn to before me this 16th day of November 1953

My Commission Expires: August 20, 1956

  
NOTARY PUBLIC