

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 N. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

0			

Locate well correctly on above Section Plat

Barton County, Sec. 11 Twp. 20 Rge. (E) 12 (W)
Location as "NE/CNW%SW%" or footage from lines. NW $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$
Lease Owner Glickman Oil Company
Lease Name Steckel Well No. 1
Office Address P. O. Box 3108, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 1-14 1957
Application for plugging filed 1-14 1957
Application for plugging approved 1-14 1957
Plugging commenced 1-14 1957
Plugging completed 1-14 1957
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	256'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Ran heavy mud to 220'. Set bottom plug with 1/3 sack hulls, 20 sacks cement, through Drill Pipe. Mud to 40', set top plug with 1/3 sack hulls, 10 sacks cement. Filled to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company
Address 915 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. Fred Hambright (employee of Lewis Drilling Company operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambright
915 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 57

My commission expires August 20, 1960

A. R. Derrington
(A. R. Derrington) Notary Public.

PLUGGING
FILE SEC. 11 T. 20 R. 12W
BOOK PAGE 134 LINE 4

FEB 18 1957
CONSERVATION DIVISION
Wichita, Kansas
2-18-1957

WELL LOG

15.009.01297.0000

COMPANY Glickman Oil Company

SEC. 11 T. 20 R. 12W
LOC. NW¹/₄NW¹/₄NW¹/₄

FARM Steckel

NO. 1

TOTAL DEPTH 3430'

DOMM. 1-5-57


COMP. 1-14-57

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

COUNTY Barton
KANSAS



ELEVATION 1802 KB

PRODUCTION

CASING

20 10
15 x 8 5/8" - 256'
12 6
13 5

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 165	Sand
165 - 290	Shale
290 - 950	Red beds
950 - 2150	Shale & Lime
2150 - 2475	Shale
2475 - 2925	Lime & shale
2925 - 3430	Lime
3430	T. D.

Geologic Tops:

Topeka	2733'
Heebner	2974'
Brown Lime	3094'
Lansing Kansas City	3113'
Conglomerate	3354'
Arbuckle	3393'

State of KANSAS }
County of SEDGWICK } ss:

PLUGGING
SEC. 11 T. 20 R. 12W
BOOK PAGE 134 LINE 4

RECORDED
STATE COMMISSION

FEB 12 1957

CONSERVATION DIVISION
Wichita, Kansas

I, J. Fred Hambright of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Steckel #1 well.

J. Fred Hambright
(J. Fred Hambright)

Subscribed and sworn to before me this 17th day of January 1957

My Commission Expires: August 20, 1960

A. R. Derrington
NOTARY PUBLIC
(A. R. Derrington)