

## ÖR

**Strike out upper line when reporting plugging off formations.**

NORTH

[illegible]

Locate well correctly on above  
Section Plat

Barton County. Sec. 11 Twp. 20 Rge. 12 ~~XX~~ (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines CWL, SW $\frac{1}{4}$ , NE $\frac{1}{4}$

Lease Owner: Gerbrand-Pulse Oil & Drlg. Co

Lease Name Fred Steckel Well No 1

Office Address.....Hoke Bldg. Hutchinson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole).....Dry

Date, well completed. 11/29/39 193

Application for plugging filed 11/29/39 193

Application for plugging approved.....	193
--	-----

Plugging Commenced	11/29/39	193
--------------------	----------	-----

Plugging Completed	11/29/39	193
--------------------	----------	-----

Reason for abandonment of well or producing formation.....

If a producing well is abandoned, date of last production.....193.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well..... C. J. Alexander

Producing formation..... Depth to top 3351' Bottom 3404' Total Depth of Well 3404' Feet

Show depth and thickness of all water, oil and gas formations.


## OIL, GAS OR WATER RECORDS

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled from bottom to 134' with heavy rotary mud. Plug set at 134'. Cemented 8 sacks. Heavy mud to within 5' of top, cemented 4 sacks 10" surface pipe cased and welded.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... Gerbrand-Pulse Oil & Drlg. Co

Address.....Hoke Building, Hutchinson, Kansas

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_ ss.

..... (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_

(Address)

SUBSCRIBED AND SWORN to before me this 21 day of December 19 39

My commission expires **My Commission Expires June 13, 1942**

18-357

7-39—3M

Notary Public.

15.009.14489.0000

LOG: STECKEL #1, CWL, SW  $\frac{1}{4}$ , SE  $\frac{1}{4}$ , SEC. 11, TWP. 20, RGE. 12, BARTON COUNTY KANS.

DRILLERS: GERBRAND-PULSE OIL & DRILLING CO., HUTCHINSON, KANSAS.

COMMENCED: NOV. 16, 1939

COMPLETED: NOV. 29, 1939

Surface Sand	134'
Sandy Shale	200
Sand	240
Red Bed & Shells	568
Anhydrite	605
Shale and Shells	1385
Broken Lime	1525
Lime	1610
Sand	1637
Shale	1725
Lime	1825
Sandy Shale	1835
Shale	1850
Lime	1980
Broken Lime	2045
Shale and Shells	2295
Broken Lime	2665
Lime	2740
Broken Lime	2850
Lime	2920
Broken Lime	3080
Shale and Shells	3110
Lime	3245
Broken Lime	3345
Lime	3351
Arbuckle	3351 - 3404
Slight show of oil in core 3354 to 3355	
Slight show oil in core at 3370	

- - CASING RECORD - -

134' of 10" 40#, 8 Thread, Cemented 140 sacks

I, Clyde Pulse, Manager of the Gerbrand-Pulse Oil & Drilling Company, do hereby certify that this is a true and correct log of the formation encountered on the above mentioned well as taken from the daily drilling reports thereon.

SIGNED

Clyde Pulse  
Manager.

SUBSCRIBED AND SWORN TO BEFORE ME  
THIS 1st DAY OF Dec, 1929

B. Alice Smith  
Notary Public  
My Commission Expires June 13, 1942