


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 11 Twp. 20SRge. 12W(E) (W)  
Location as "NE/CNW/SW" or footage from lines SW NE NE  
Lease Owner ALPINE OIL & ROYALTY CO., INC.  
Lease Name WOODMANSEE "B" Well No. 2  
Office Address 800 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 1, 1961 19  
Application for plugging filed April 1, 1961 19  
Application for plugging approved April 1, 1961 19  
Plugging commenced April 1, 1961 19  
Plugging completed April 1, 1961 19  
Reason for abandonment of well or producing formation non-productive in commercial quantities  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3390 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	163	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud from total depth - 3390 feet to 160; 1/4th sacks hulls and plug at 160 feet and 25 sacks cement through drill pipe. Mud to 40 feet 1/3rd sack hulls and plug; 10 sacks cement 2 sacks to plug rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

APR 11 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Quaker Drilling Co., Inc.  
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.  
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul  
800 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of April, 19 61

My commission expires August 10, 1961 Quinn Marshall Notary Public.



## WELL LOG

ALPINE OIL &amp; ROYALTY CO., INC.

Commenced: March 24, 1961

Contractor: Quaker Drilling Co., Inc.

Completed: April 1, 1961

Woodmansee No. 2-B  
SW NE NE Sec. 11-20S-12W  
Barton County, Kansas

Elevation: 1797 K. B.

## Casing Record

Set 8 5/8 inch casing at 163 feet with 175 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Sand	118	Heebner	2963 -1166
Blue Shale	163	Brown Lime	3084 -1287
Blue Shale, Sand & Red Bed	575	Lansing	3102 -1305
Anhydrite	602	Base of Kansas City	3339 -1532
Red Bed	725	Conglomerate	3347 -1550
Shale and Shells	1205	Arbuckle	3353 -1556
Sandy Lime & Shale	1550	Rotary Total	
Lime and Shale	1880	Depth	3390 -1593
Shale and Shells	2230		
Shale and Lime	2585		
Lime	2690		
Lime and Shale	2790		
Lime	2934		
Lime and Shale	3187		
Lime	3263		
Lime	3353		
Dolomite	3390		

RECEIVED  
STATE CORPORATION COMMISSION

APR 11 1961

CONSERVATION DIVISION  
Wichita, Kansas


We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SW NE NE of Section 11, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By:

  
 Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 4th day of April, 1961.

  
 Virginia Mundell, Notary Public
MY COMMISSION EXPIRES:  
August 10, 1961