

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

Rice

County, Sec. 36 Twp. 20 Rge. 8 (EX) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE NW SE

Lease Owner Carlock & Dufton

Lease Name L. Renollet Well No. 1

Office Address Ellis-Singleton Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date, well completed January 1 19 40

Application for plugging filed April 5 19 41

Application for plugging approved April 5 19 41

Plugging Commenced April 10 19 41

Plugging Completed April 11 19 41

Reason for abandonment of well or producing formation Non-production

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, M. Pherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. The table is currently empty.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Total depth 3322'
5 1/2" casing at 3317', 10 3/4" casing at 130'
Plug (4 sacks) mud to 3317', cement from 3317' to 3285'
Plug (10 sacks) mud from 3285' to 130'; cement from 130' to 110'
Cap (6 sacks) mud from 110' to 14' cement from 14' to cellar base


pd. 5/8/41



5-8-1941

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Goldenstern-Silver, Inc. Address Box 921, Wichita, Kansas



STATE OF KANSAS, COUNTY OF SEDGWICK, ss. William Pinsker

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William Pinsker

Box 921, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 8th day of May 1941

Emoquell Whitcomb Notary Public

My commission expires Nov. 25, 1943

Carlook & Dufton  
L. Renollet No. 1

36-20-8W  
W<sub>2</sub> SD<sub>4</sub>

15,159.05039.0000  
Rice County, Kans.

Contractor: Gerbrand-Pulse Oil & Drilg. Co.

Comm: 11-20-39  
Comp: 1-4-40

CASING RECORD

10", 40#, 8 Thd. 130'  
Cemented 130 sacks cement  
5 1/2", 17#, 10 Thd. Seamless  
casing, 3317'  
Cemented 75 sacks (IDEAL)

surface and sand	131'
red rock and shells	400
shale and shells	620
shale, shells & salt	825
shale and shells	1050
lime	1230
broken lime	1265
shale and sand	1395
lime	1405
shale	1500
lime	1540
shale and shell	1555
shale	1630
broken lime	1685
shale	1940
shale and shell	1980
shale	2475
lime	2805
shale	2955
lime	3065
shale and shells	3095
shale & lime	3140
lime	3185
shale and lime	3222
shale	3294
varigated shale	3317
conglomerate	3322

Well flowed

State Potential: 502 barrels.

