

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rice SEC. 25 TWP. 20 RGE. 10 NE/W
Location as in quarters or footage from lines:
C E/2 NW SW

Lease Owner Woodman & Iannitti Drilling Company
 Lease Name Malone "B" Well No. 1-25
 Office Address 1008 Douglas Bldg., Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed February 4, 1983
 Application for plugging filed February 4, 1983
 Plugging commenced February 4, 1983
 Plugging completed February 4, 1983
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3390
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug @ 310' w/50 sx.
2nd Plug @ 40' w/10 sx.
3rd Plug @ Rathole w/10 sx.
Plug down @ 2:45 PM., February 4, 1983
Plugged w/ 70 sacks 50/50 Pozmix, 2% Gel, 3% CC

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing


STATE OF Kansas COUNTY OF Sedgwick, ss.
K.T. Woodman (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) K.T. Woodman
1008 Douglas Bldg., Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of February, 19 83

Kathryn A. Voigt
 Notary Public.

My Commission expires: April 20, 1985 Kathryn A. Voigt



K. T. WOODMAN
 RES. PHONE 733-0418
 OFF. PHONE 265-7650
 WICHITA, KANSAS

D. J. IANNITTI
 PHONE 792-2921
 GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

1008 DOUGLAS BUILDING
 104 S. BROADWAY
 WICHITA, KANSAS 67202

February 17, 1983

Company:	Woodman & Iannitti Drilling Company
Farm:	Malone "B" #1-25
Location:	C E/2 NW SW
Section:	25-20-10W
County:	Rice
Contractor:	Woodman & Iannitti Drilling Company
Total Depth:	3390'
Comm:	January 25, 1983
Comp:	February 4, 1983
Casing:	8-5/8" 24# set @ 201'

Figures Indicate Bottom Formations:

209	Shale & Clay
275	Shale
375	Shale & Red Bed
383	Anhydrite
860	Shale
1400	Shale
1770	Lime & Shale
2075	Lime & Shale
2330	Shale
2500	Lime & Shale
2625	Lime & Shale
2820	Lime & Shale
2980	Lime
3085	Lime
3200	Lime
3256	Lime
3320	Lime
3330	Lime
3350	Congl.
3390	Arbuckle

I certify the above to be a true and correct copy of the Drillers Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

K.T. Woodman
 K.T. Woodman, Partner

Sun Oilwell Cementing
A Division of BJ Hughes, Inc.

15.159.21552.0000

P. O. Box 169
GREAT BEND, KANSAS 67530

CEMENTING TICKET
and Invoice Number

VAC. 1/2/78

No. 14171

Date 2-1-83	Customer Order No.	Sec. 35	Twp. 20	Range 10	Truck Called Out 7:30 AM	On Location 11:00 AM	Job Began 2:00 PM	Job Completed 2:45 PM
----------------	--------------------	------------	------------	-------------	-----------------------------	-------------------------	----------------------	--------------------------

Owner WOODMAN LAMBERTI	Contractor W&J DRILL #2	Charge To WOODMAN - JANU 1983
Mailing Address	City	State

Well No. and Farm WILSON B-1-25	Place KANSAS 2E 20 E-3	County RICE	State KANSAS
------------------------------------	---------------------------	----------------	-----------------

Depth of Well 3390	Depth of Job	Casing New Size _____ Used Weight _____	Size of Hole Amt. and Kind of Cement 7 7/8 70 SK	Cement Left in casing by	Request Necessity _____ feet
-----------------------	--------------	---	---	--------------------------	------------------------------

Kind of Job PLUG TO ANNULAR	Drillpipe 4 1/2	Rotary Cable	Truck No. 30
--------------------------------	--------------------	--------------	--------------

Condition of Well at time of Cementing: D-H
Typ of Plugs: 1/2 DRY HOLE PLUG

Pressure Circulating: Minimum _____ Maximum _____

Time Required Mixing Cement _____ min. Making Change _____ min. Pumping Cement _____ min.

Remarks: 1st 50 SKS AT 310'
10 SK AT 40' SOLID BRIDGE
10 SKS IN NAT HOLE

Price Reference No. #9
Price of Job 370.00
Second Stage
Standby Truck
Other Charges
Pump Truck Mileage 36.00

CEMENTED WITH 70 SKS 750
NO. 320 CASK. 290 GEN
THANK YOU

Cementer: HAMMER Material Left on Location

Helper: STEVE District: GREAT BEND State: KANSAS

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.

State Pluggers on Location Yes No

Prices Subject to Correction. Agent of Contractor or Operator

SALES TICKET FOR MATERIALS

QUANTITY SACKS	BRAND AND TYPE	PRICE	TOTAL
35 SKS	Hammer		
36 SKS	NO. 2		
Ce Cl.	176		
AM. Cl.			
Gel	110		
Plugs	1- 1/2 DRY HOLE PLUG		
Delivered by Truck No.	B-25	Handling and Dumping Mileage	24
Delivered From	GREAT BEND	Sales Tax	
Signature of Operator	KIMMAY	Total Charges	