

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 1500 924 254-0000 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Ramco Drilling Service, Inc. OPERATORS LICENSE NO. 3536

ADDRESS P. O. Box 99, Belpre, Ohio 45714 PHONE # (614) 423-9591

LEASE (FARM) William Welsh WELL NO. 1 WELL LOCATION C-S/2-S/c-SE COUNTY Barton

SEC. 11 TWP. 20 S RGE. 13 (E) or (W) TOTAL DEPTH 3526' PLUG BACK TD 3330'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 260 CEMENTED WITH 190 SACKS

CASING SIZE 5 1/2" SET AT 3521' CEMENTED WITH 125 SACKS

PERFORATED AT 3213' - 3219'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 50' of sand over top perfs in Kansas

City at 3213-19', Dump 5 sacks cement on top of sand, top cement at 3177'.

Pump 4 sacks of hulls and 100 sacks of econo lite cement to top.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10 am. 10-28-87

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

D S & W Well Servicing, Inc.

PHONE # (316) 587-3361 RECEIVED
OCT 30 1987 10-30-87
COMMISSION

ADDRESS P. O. Box 231 Claflin, Kansas 67525

PLUGGING CONTRACTOR D S & W Well Servicing, Inc. LICENSE NO. 6690 CONSERVATION DIVISION
Wichita, Kansas

ADDRESS Claflin, Kansas 67525 PHONE # (316) 587-3361

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

DATE: 10/28/87