

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Compt. _____

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6420 EXPIRATION DATE 6/30/83

OPERATOR K.R.M. PETROLEUM CORPORATION API NO. 15-135-22,394

ADDRESS 1900 Grant Street, Suite 300 COUNTY Ness
Denver, Colorado 80203 FIELD Wildcat

** CONTACT PERSON James Alan Townsend PROD. FORMATION --
PHONE 303/830-6601

PURCHASER NA LEASE Scully

ADDRESS WELL NO. 1-10

DRILLING ALDEBARAN DRILLING COMPANY WELL LOCATION 300' W & 200' N of
CONTRACTOR 460' Ft. from west C SW SW Line and

ADDRESS P.O. Box 18611 960' Ft. from south Line of (W)
Wichita, Kansas 67207 the SW/4 (Qtr.) SEC 10 TWP 19S RGE 26 (W).

PLUGGING CONTRACTOR ADDRESS

WELL PLAT

(Office Use Only)

		10	

KCC
KGS
SWD/REP
PLG.

TOTAL DEPTH 4616' PBTD -

SPUD DATE 5/27/83 DATE COMPLETED 6/7/83

ELEV: GR 2614' DF KB 2624'

DRILLED WITH (CABLE) - (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 378' DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, (Dry) Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

James Alan Townsend, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

James Alan Townsend
(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 27th day of June, 1983.

Matthew Sidel
(NOTARY PUBLIC)

MY COMMISSION EXPIRES: 8-8-84

RECEIVED
STATE COMMISSION
1983 Grant St
Wichita, KS 67202

** The person who can be reached by phone regarding any questions concerning this information.

JUN 30 1983

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 1-10

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				
DST #1: 4567'-4571' (Mississippi) IHP=2154, 30" IFP=11-119, 60" ISIP=1241, 65" FFP=217-334, 126" FSIP=1253, FHP= 2127, rec. 90' CO, 810' SOCW.			Anhydrite	1890 (+737)
			Heebner	3904 (-1280)
			Toronto	3930 (-1310)
			LKC	3952 (-1328)
			Stark	4211 (-1587)
			Swope	4220 (-1596)
			Hush	4250 (-1626)
			Hertha	4262 (-1638)
			BKC	4302 (-1678)
			Marmaton	4334 (-1710)
			Pawnee	4414 (-1790)
			Ft. Scott	4470 (-1846)
			Cherokee	4492 (-1868)
			Reworked Miss.	4564 (-1940)
			Mississippi	4570 (-1946)
Ran Dresser Atlas, Dual Induction Focused Log and Compensated Densilog, Compensated Neutron Gamma Ray Log.				

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
surface	12 1/4"	8-5/8"	23#	378'	C1. "A"	230	2% gel & 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production Well P & A 6/7/83	Producing method (flowing, pumping, gas lift, etc.)	Gravity
Estimated Production -I.P.	Oil bbls.	Gas MCF
	Water %	Gas-oil ratio
Disposition of gas (vented, used on lease or sold)		Perforations

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY NESS SEC. 10 TWP. 19S RGE. 26W E/W
Location as in quarters or footage from lines:
200'W & 200'N of C SW SW

Lease Owner KRM PETROLEUM CORPORATION
Lease Name SCULLY Well No. #1-10
Office Address 1900 GRANT ST., SUITE 300, DENVER, COLO. 80203
Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE
Date Well Completed June 7, 1983
Application for plugging filed July 1, 1983
Plugging commenced 4:45 P.M. June 7, 1983
Plugging completed 6:45 P.M. June 7, 1983
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Permission was obtained

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	378	J-55	9 Joints	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged well with 215 sks 60-40 pos, 2% gel, 3% cc, plugs
were staged at 50 sks at 1710', 50 sks at 1140', 40 sks
at 540', 10 sks at 40', 15 sks rat hole & 10 sks mouse hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton-Ness City

STATE OF Kansas COUNTY OF Sedgwick, ss.

Deborah Bryant (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) _____
453 S. Webb Rd., Box 18611
Wichita (Address) Kansas 67207

SUBSCRIBED AND SWORN TO before me this 1st day of July, 19 83

Kathleen G. Quinn RECEIVED
KATHLEEN G. QUINN STATE CORPORATION COMMISSION

My Commission expires: March 20, 1987



JUL 05 1983

CONSERVATION DIVISION
Wichita, Kansas