



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 21 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. A. C. Radke of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Petroleum, Inc. guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 W. Douglas, Wichita, Kansas 67202

Lease Name: Schumacher "E" Well No. # 1

Location: SW SE NW Sec. 30 Twp. 20 Rge. 13 (E)(W) W

County: Barton Total Depth 3558 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. A. C. Radke was instructed to plug the well as follows:

8 5/8" 215' Cwc.

Circulated hole with heavy mud to 400', set plug, & displaced 25 sax

cement thru drill pipe. Mud to 200' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Globe Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don Truman  
Conservation Division Agent