



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Leo J. Dreiling of Leo J. Dreiling Oil Co. has this date requested permission to plug the following described well:

Mr. Leo J. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling

Complete Address: R. R. # 2, Victoria, Kansas 67671

Lease Name: Christiansen Well No. # 2

Location: 100' SNW NE NW Sec. 13 Twp. 20 Rge. 13 (E)(W) W

County: Barton Total Depth 3470 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Russ Sullivan was instructed to plug the well as follows:

8 5/8" 221' Cwc.

Sanded hole back to 3150' & dumped 4 sax cement with dump bailer.

Pulled pipe. Squeezed well with 20 sax mud & 90 sax cement with

Sun Cementing Company's pump truck, cementing from 300' to base

of cellar.

Very truly yours,

David L. Brown
Conservation Division Agent