



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Donald L. Ingling guarantees payment of the plugging fee.

Operator's full Name: Donald L. Ingling

Complete Address: 615 1st. Nat'l. Bldg., Wichita, Kanas 67202

Lease Name: Panning Well No. # 1

Location: C E/2 NW N1/4 Sec. 12 Twp. 20 Rge. 13 (E)(W)W

County: Barton Total Depth 3460 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fred Cameron was instructed to plug the well as follows:

8 5/8" 208' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 200' & displaced 25 sax cement thru drill

pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with

Globe Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don L. Luman
Conservation Division Agent