

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Aspen Drilling Company

Complete Address Box 783 Great Bend, Kansas

Lease Name Dinges Well No. 1

Location NW SW Sec. 21 Twp. 9 Rge. (E) (W) 25

County Ness Total Depth 4625

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 6P Day 1 Month 11 Year 1969

The above well was plugged as follows:

RTD 4625' 8 5/8 csg set at 402' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 375' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar/

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Mussey
Well Plugging Supervisor

DATE 11/6/69
INV. NO. 980-4