

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 66-10

LOCATION new-new-new

SEC. 18 TWP. 20 RGE. 18

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Harrison

Operator J. Goldstein Address 313-Boston Bldg Denver Colorado

Field \_\_\_\_\_ County Barton

Total Depth 3555 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 1000ft. Circulated with cement.  
5 1/2" casing set at 2555ft - 100 sacks of cement -  
Plugged back to 3525ft with sand & chat. Dumped  
4 sacks of cement at 3525ft - Shot off & pulled the  
5 1/2" casing - mud to 300ft - Set rock bridge &  
20 sacks of cement at 300ft. mud to 25ft - Plug &  
10 sacks of cement at the surface -  
R & S. Pipe Pulling Co. Plugging Contractor

**PLUGGING**  
FILE REC 12 1952 R 137  
BOOK PAGE 66 LINE 10

12-29-52  
**RECEIVED**  
STATE CORPORATION COMMISSION  
DEC 29 1952  
CONSERVATION DIVISION  
Wichita, Kansas

C. M. Stough  
District Conservation Agent  
Date 12-26-52