

KANSAS

FORM CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Ks. 67202

API Number 15 -009-21511.0000 (of this well)

Operator's Full Name Petroleum Energy, Inc.

Complete Address 710 One Twenty Bldg., Wichita, Kansas 67202

Lease Name Hart Well No. 1

Location 175' E of SW NE NW Sec. 17 Twp. 20 Rge. 13 (E) (W) X

County Barton Total Depth 3580'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D&A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1:30 Day 25 Month 9 Year 1980

The Above well was plugged as follows:

Sanded back to 3200' and 4 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 5 sx hulls,

25 sx mud-gel, plug, and 125 sx cement.

Max. pres. 400#. Shut in pres. 100#.

Recovered 2526' of 4 1/2" casing.

plugged back to 3255'. Top perforation at 3241'.

3579' of 4 1/2" casing.

243' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

Signed: Duane A. Rankin  
Well Plugging Supervisor

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 30 1980  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 10-2-80  
INV. NO. 3237W