

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-113-20,755

LEASE NAME NORMAN VOGTS

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER 1

SPOT LOCATION 600' from 1,330' well
NE NW

SEC. 17 TWP. 20 RGE. 1W (E) OR (W)

LEASE OPERATOR KOEHN OIL CO.

COUNTY MCPHERSON

ADDRESS RT. 2 BOX 89 GALVA, KS 67443

DATE WELL COMPLETED 9-4-80

PHONE # (316) 654-3872 OPERATORS LICENSE NO. 5217

PLUGGING COMMENCED 8-23-83

CHARACTER OF WELL OIL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMPLETED 8-26-83

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? YES

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? DIST. # 5

IS ACC-1 FILED? IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION DEPTH TO TOP BOTTOM T.D. 3065'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2,015.20'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. SANDED BACK TO 2960' WITH 4 SACKS CEMENT

MUDDERED HOLE TO 280' MADE 15' ROCK BRIDGE AND FILLED WITH 4 1/2 YDS. OF READY MIX.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR H&H CASING PULLING CO. LICENSE No. 6053
ADDRESS 1427 N. HALSTEAD HUTCHINSON, KS. 67501

STATE OF KANSAS COUNTY OF RENO, SS.

DONALD H. HURST (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Donald H. Hurst
FINEST MOBILE HOME PARK TOT# 78
(ADDRESS) GREATBEND, KS. 67530



MY COMMISSION EXPIRES:

SUBSCRIBED AND SWORN TO BEFORE ME THIS 27th DAY OF August, 1983
Madeline Hurst
NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1983

CONSERVATION DIVISION
WICHITA, KANSAS

FORM CP-4
REVISED 06-83

15.113.20755.0000



Rodell Kocher
Open file 3217

Blackstone Drilling, Inc.

Box 1184 • 528 West Kansas • Phone (816) 241-1250
McPHERSON, KANSAS 67460

API # 15-113-20755

September 5, 1980

Drill well in NE 1/4 Sec 17, T. 20 N., R. 17 W., McPherson County, Kansas

COMPANY: E. K. LOEWEN

CONTRACTOR: BLACKSTONE DRILLING, INC.

FARM: NORMAN VOETS #1

LOCATION: 800' SWL & 330' WEL NE NW Section 17-20-1W, McPherson County, Kansas

COMMENCED: August 30, 1980

COMPLETED: September 4, 1980

ELEVATION: 1870 K. B.

0	to	70	RECEIVED STATE CORPORATION COMMISSION	Sand
70	to	180		Blue Shale
180	to	1570	AUG 29 1983	Line & Shale
1570	to	1920		Shale & Line
1920	to	2072	CONSERVATION DIVISION Wichita, Kansas	Line & Shale
2072	to	2695		Shale & Line
2695	to	2810	Line & Shale	
2810	to	2941	Shale & Line	
2941	to	3030	Mississippi	
3030	to	3065	Line	
		3065	T. D.	

Set hole to 166' & run 166' of 8 3/8" surface pipe, cemented with 100 sacks of cement. Plug down at 5:30 P. M., August 30, 1980. Run 3072' of 4 1/2" casing, cemented with 75 sacks of cement, 1 foot off bottom at 3064'. Plug down at 2:30 P. M., September 5, 1980.

TOPS: LANING - 2343' MISSISSIPPI - 2947'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Ploeffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a correct copy of log on your Norman Voets #1, located on the NE NW Section 17-20-1W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc..


Page 3011-20

P. E. Ploeffe
P. E. Ploeffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 5th day of September, 1980.

Plug back to 2960 (M) 4 sacks

Johnnie L. Schmidt
Johnnie L. Schmidt - Notary Public



*From Sdwa, Ks.
Black top east of town go N. 1/2. N 1/2 East on So. side
of Rd.*