

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15.009.20434.0000

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Welsh #2

WELL NUMBER _____

SPOT LOCATION NW SE SE

SEC. 11 TWP. 20 RGE. 13w (E) OR (W)

COUNTY Barton

DATE WELL COMPLETED _____

PLUGGING COMMENCED 9/19/83

PLUGGING COMPLETED 10/13/83

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947, Pratt, Kansas 67124

PHONE # () _____ OPERATORS LICENSE NO. _____

CHARACTER OF WELL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays

IS ACG-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 3490'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	195'	none
				4 1/2"	3465'	1065'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Plugged off bottom with 4 sacks cement, sanded back to 3350' & 4 sacks cement. Shot pipe at 2688', 2388', 2278', 2171', 1886', 1710', 1567', & 1073'. Pulled 33 joints. Plugged well with 4 hulls, 25 cement, 12 gel, 40 cement, 35 gel, 1 hull, released plug & 100 sacks 50/50 poz 4% gel 3% c.c. Plugging complete.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050
ADDRESS Box 347, Chase, Ks. 67524


STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 18th DAY OF October, 1983



RECEIVED
Irene Hoover
STATE CORPORATION COMMISSION
NOTARY PUBLIC

OCT 1 0 1983

MY COMMISSION EXPIRES: _____

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Company
 Victoria, Kansas

Sec. 11 Twp. 20 Rng. 13

Farm Welch No. 2

Location NW SE SE

Total Depth 3490'

County Barton

Comm. 9-19-66 Comp. 9-26-66

1858' K.B.

Elevation: 1855' D.F.

Contractor L.J. Dreiling & Sons, Inc.
 Victoria, Kansas

1853' G.R.

Casing Record

Cement Record

Production:

195' 8-5/8"
 3465' 4 1/2"

200 sacks
 100 sacks

Figures Indicate Bottom of Formations

0'	180'	Sand & Gravel
180'	198'	Blue Shale
198'	630'	Shale-Sand-Red Bed
630'	670'	Red Bed
670'	695'	Anhydrite
695'	1522'	Shale & Red Bed
1522'	1585'	Lime
1585'	1777'	Lime & Shale
1777'	1953'	Lime & Shale
1953'	2235'	Shale & Lime
2235'	2538'	Shale W/Lime Strks.
2538'	2687'	Shale & Lime
2687'	2920'	Lime & Shale
2920'	3017'	Shale & Lime
3017'	3075'	Shale & Lime
3075'	3125'	Lime & Shale
3125'	3225'	Lime
3225'	3280'	Lime
3280'	3295'	Lime
3295'	3380'	Lime
3380'	3392'	Lime
3392'	3490'	Lime
3490'	R.T.D.	

RECEIVED
 STATE COMMISSION
 MAR - 5 1966
 CONSERVATION DIV.
 WICHITA, KANSAS

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Welch # 2.

Leo F. Dreiling
 LEO F. DREILING

Subscribed and sworn to before me this 29th day of September, 1966.

Elmer Welch
 NOTARY PUBLIC

My commission expires: October 26, 1968