

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

15.009-23444.0000
WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,444

LEASE NAME Welsh "B"

WELL NUMBER #1

SPOT LOCATION NE SE SE

SEC. 11 TWP. 20 RGE. 13 (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 4-6-84

Plugging Completed 4-17-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Carrol Oil Production, Inc.

ADDRESS Box 1987, Great Bend, Kansas 67530

PHONE # () 793-7156 OPERATORS LICENSE NO. 8318

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 6

Is ACO-1 filed? Yes if not, Is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3567'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	326'	None
				5-1/2"	3,565'	2,531.79'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped 5 sacks cement on bottom. Sanded back to 3180' and dumped 5 sacks cement. Shot casing at 2700' and 2540'. Pulled 64 joints of 5-1/2" casing. Squeezed well with 3 sacks hulls, 9 sacks gel, 80 sacks cement and 6 sacks gel, blended with 2 sacks hulls, released plug and pumped 70 sacks 50/50 pozmix cement with 10% added gel and 3% calcium chloride.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(employee of operator) of CONSERVATION DIVISION
(operator) of above-described well, being first duly sworn on oath, says: That Wichita, Kansas
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Great Bend, Ks.
67530

SUBSCRIBED AND SWORN TO before me this 18th day of April, 1984

My Commission expires:

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public