

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15.009.00769.0001

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Welsh #1

WELL NUMBER _____

SPOT LOCATION SE SE SE

SEC. 11 TWP 20 RGE. 13w (E) OR (W)

COUNTY Barton

DATE WELL COMPLETED _____

PLUGGING COMMENCED 9/23/83

PLUGGING COMPLETED 10/13/83

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947, Pratt, Kansas 67124

PHONE # () _____ OPERATORS LICENSE NO. _____

CHARACTER OF WELL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays

IS ACO-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 3510'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	188'	none
				5 1/2"	3509'	1986'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Ran 5 sacks cement, sanded, & 5 more sacks cement on top, back to 3200'. Short pipe at 1987'. Pulled total of 62 joints. Plugged well with 4 hulls, 25 cement, 12 gel, 40 cement, 3 gel, 1 hull, released plug & 100 sacks 50/50 poz 4% gel 3% c.c. Plugging complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 18th DAY OF October, 19 83



NOTARY PUBLIC

MY COMMISSION EXPIRES: _____

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1983

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83

10-19-1983