


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 18 Twp. 20 Rge. 13 (E) W (W)
Location as "NE/CNWSW" or footage from lines SW - SW - NW
Lease Owner Frontier Oil Co. Frontier Oil Co.
Lease Name Harrison Well No. 2
Office Address Wichita, Kansas 580 Fourth National Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced June 4 19 62
Plugging completed June 11 19 62
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3589 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3589 feet to Surface feet for each plug set.

Well had been plug back to 3480, Sand up to 3230. Per. at 3244, 5 sacks of cement dump on bottom. Shot pipe off at 2899 & pulled from hole. Mudded up to 460' IO' rock bridge, Put 6 Yds. Of concret in hole up to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

George A. Angle (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
580 Fourth Natl. Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 19 62

My commission expires 11-17-62.

Dannie Head
Notary Public.



DRILLERS LOG

No. 2 Harrison

CASING RECORD: COMPANY: Frontier Oil Company DESCRIPTION: SW SW NW
 8 5/8" @ 791' CONTRACTOR: Red Tiger Drilling Co. 18-20S-13W
 w/200 sx cement Barton County,
 Kansas
 COMMENCED: Sept. 9, 1958
 5 1/2" @ 3590' ELEVATION: 1882 DF
 w/125 sx cement COMPLETED: Sept. 19, 1958 1885 RB
 781
 1124

TOTAL DEPTH: 3590' (-1705)

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod and Sand	0	150	
Shale and Shells	150	260	
Sand	260	295	
Shale and Shells	295	430	
Shale and Sand Streaks	430	565	
Red Bed Shale	565	781	
Anhydrite	781	807	
Shale and Shells	807	1600	
Lime and Shale	1600	2990	
Lime	2990	3513	
Arbuckle	3513	3590	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

George A. Angle
 George A. Angle

Subscribed and sworn to before me this 23rd day of September, 1958.

James Head
 Notary Public

My Commission Expires:

11-17 58