

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH

Barton County. Sec. 18 Twp. 20 Rge. 13 (W) (N)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SE NE NE

Lease Owner Mallard Drg. Co. & Westgate-Greenland Oil Company

Lease Name Harrison Well No. 1

Office Address 1016 Union National Bank Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed December 4 19 48

Application for plugging filed December 4 19 48

Application for plugging approved " 19 48

Plugging commenced " 19 48

Plugging completed " 19 48

Reason for abandonment of well or producing formation.....

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes--oral

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3617 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				300 ft.	8 5/8	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole full heavy mud to within 300 feet of top.
Drove wooden plug to 300 feet of top, put in 20
sacks cement and finished filling hole full heavy
mud to within 15 ft. of top of cellar and put in
5 sacks cement.

RECEIVED
 DEC - 8 1948
 STATE CORPORATION
 COMMISSION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mallard Drilling Company
 Address 1016 Union National Bank Bldg.


STATE OF Kansas COUNTY OF Sedgwick, ss.
C. C. Nelson, partner (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. C. Nelson

SUBSCRIBED AND SWORN to before me this 8th day of December, 1948 (Address)
Hapwell Wright
 Notary Public.

My commission expires 12/4/52



COMPANY: Mallard Drilling Company
 Westgate-Greenland Oil Company
 Contractor: Mallard Drilling Company
 Well: Harrison #1
 LOCATION: SE NE NE: Section 18-20-13W
 Barton County, Kansas
 COMMENCED: November 22, 1948
 COMPLETED: December 4, 1948

0	to	300	Surface sand
300	to	720	Shale
720	to	1190	Shale and shells
1190	to	1575	Shale and shells
1575	to	1735	Lime
1735	to	2070	Lime
2070	to	2635	Lime and shale
2635	to	2795	Shale and lime
2795	to	3020	Lime
3020	to	3130	Lime
3130	to	3245	Shale and lime
3245	to	3248	K.C. Lime
3248	to	3318	Lime
3318	to	3433	Lime
3433	to	3475	Lime
3475	to	3503	Conglomerate
3503	to	3533	Conglomerate
3533	to	3578	Cherty Conglomerate
3578	to	3585	Conglomerate
3585	to	3617	Arbuckle
		3617	S.D.

Set 300 feet of 8 5/8" surface pipe. Cemented with 175 sacks cement.

TOPS: K.C. Lime--3245 Arbuckle--3585

Measurements taken from top of derrick floor.

DRY, ABANDONED AND PLUGGED

RECORDED

DEC - 5 1948

314

NOTARY

C E R T I F I C A T E

KANSAS

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Harrison #1, Section 18-20-13W, Barton County, Kansas, as reflected by files of the Mallard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 20th day of December 1948.

Harwell Wright

My commission expires 12/4/48

