


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barton County. Sec. 17 Twp. 20 Rge. 13 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner Petroleum, Inc.  
Lease Name Titus 'D'  
Office Address 100 Derby Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 19, 1952  
Application for plugging filed May 19, 1952  
Application for plugging approved May 19, 1952  
Plugging commenced May 19, 1952  
Plugging completed May 19, 1952  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough  
Producing formation Depth to top Bottom Total Depth of Well 3540 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 224'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 210' with heavy mud, and  
placed first wooden plug at 210'. Cemented  
and displaced 20 sacks cement through drill  
pipe on top of plug at 210'. Mudded up to  
35' and placed second wooden plug at 35'.  
Filled hole to base of cellar with 10 sacks  
cement.

RECEIVED  
MAY 23 1952  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

Name of Plugging Contractor Garvey Drilling Company  
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.  
W. W. Fisher (employee of owner) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) W W Fisher  
100 Derby Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 19 52

My commission expires October 13, 1954  
Charlotte Friedman  
Notary Public.

PLUGGING  
FILE SEC-17 T-20 R-132  
BOOK PAGE-17 LINE-18

15.009.00143.0000

DRILLER'S LOG TITUS 'D' #1

Petroleum, Inc., Lease Owner

Section 17, Twp. 20S, Rge. 13W

Garvey Drilling Company, Contractor

Location: SE SE NW

Drilling Commenced: May 7, 1952

County: Barton County, Kansas

Drilling Completed: May 18, 1952

R.T.D. 3540'

Casing Record: 8 5/8" @ 224' w/175' sax

Production: D &amp; A

Figures below indicate bottom of formations:

300 Shale & Shells  
 342 Red Bed  
 750 Red Bed & Shells  
 772 Anhydrite  
 1600 Shale & Shells  
 2901 Lime & Shale  
 2985 Lime  
 3053 Lime & Shale  
 3102 Lime  
 3190 Lime & Shale  
 3216 Shale  
 3540 Lime  
 3540' R.T.D.

## Tops:

Heebner: 3107 (-1234)

Brown Limes: 3220 (-1347)

Lansings: 3233 (-1360)

Arbuckle: 3489 (-1616)

DST #1, 3221-64, open 1 hr., rec. 360'  
 gas plus 50' very slightly oil  
 cut mud, 200# BHP.

DST #2, 3314-3359, open 40 mins., rec.  
 30' mud, 1200# BHP.

DST #3, 3356-3406, open 1 hr., rec.  
 55' oil cut mud, and 90' gas,  
 170# BHP.

DST #4, 3494-3507, open 1 hr., rec. 45'  
 oil cut mud, 75 # BHP.

DST #5, 3497-3519, open 1 hour, rec.  
 50' mud, 120# BHP.

DST #6, 3516-40, open 1 hour, rec. 610'  
 salt water, 900# BHP.

I hereby certify that this is a true and correct log of the  
 above mentioned well.

PETROLEUM, INC.

By

W W Fisher  
 W. W. Fisher

STATE OF KANSAS :  
 : SS:  
 COUNTY OF SEDGWICK:

Subscribed to and sworn to before me, a Notary Public in said  
 County and State, this 20th day of May, 1952.

RECEIVED  
 PLUGGING  
 STATE CORPORATION COMMISSION  
 FILE SEC 17 T 20 R 13  
 BOOK PAGE 17 LINE 1 MAY 23 1952

Charlotte Meidman  
 Notary Public

My commission expires: October 19, 1954.