

ATE OF KANSAS  
ATE CORPORATION COMMISSION  
D. S. Market, Room 2078  
chita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-23,549-0000

LEASE NAME Hart

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #2  
4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 17 TWP. 20 RGE. 13W (E) or (W)

COUNTY Barton

EASE OPERATOR Barco Energy, Inc.

DRESS P.O. Box 1557 Great Bend, Kansas 67530

PHONE (316) 792-8141 OPERATORS LICENSE NO. 31410

Character of Well Oil

Date Well Completed \_\_\_\_\_

Plugging Commenced 9-18-98

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 9-21-98

The plugging proposal was approved on \_\_\_\_\_ (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	322'	None
				5-1/2"	3579'	1800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Set CIBP @3200' and dumped 2 sks. cement on top. Shot pipe @2000', 1900', 1800', pulled up to 1575', pumped 110 sks. cement and 300# hulls, pulled to 800', pumped 35 sks. cement and 100# hulls, pulled to 375', pumped 35 sks. cement and 100# hulls, pulled to 150' and circulated cement to surface. 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 315290

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Mike's Testing & Salvage, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 22nd. day of September, 19 98

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

